

URBAN

SUMMARY OF QUANTITIES			100% MCHD SFTY-2A URBAN
CODE NO	PAY ITEM	UNITS	QUANTITY
50102400	CONCRETE REMOVAL	CU YD	3.5
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3.5
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	27,350
50501110	STRUCTURAL STEEL REMOVAL	POUND	25,630
67100100	MOBILIZATION	L SUM	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	625
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	387.5
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	34
78300105	PAVEMENT MARKING REMOVAL	FOOT	7,024
X0324952	DETOUR SIGNING	L SUM	1
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
* X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	5,626
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	1,397
Z0003600	BEAM STRAIGHTENING	L SUM	1
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1

*Specialty Items

FILE NAME = c:\pwwork\FWIDOT\COXTE\d0123288\06720	USER NAME = coxte 9-shr-500.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I RTE. 72	SECTION (84-3HB-4)-1	COUNTY SANGAMON	TOTAL SHEETS 17	SHEET NO. 3
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	SCALE:		SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72C69			
PLOT DATE = Aug-12-2009 04:23:30PM	DATE -	REVISED -	ILLINOIS FED. AID PROJECT										