

TRAFFIC BARRIER TERMINAL, TYPE 1B	
LOCATION	63100041 TRAFFIC BARRIER TERMINAL, TYPE 1B
	EACH
STA. 976+77.15 TO STA. 977+02.15, LT	1
TOTAL	1

REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL	
LOCATION	63300575 REMOVE AND RE-ERECT RAIL ELEMENT OF EXISTING GUARD RAIL
	FOOT
STA. 972+58.87 TO STA. 973+71.57, RT	112.7
STA. 975+59.88 TO STA. 976+23.46, RT	63.6
TOTAL	176.3

SHORT-TERM PAVEMENT MARKING		
LOCATION		70300100 SHORT-TERM PAVEMENT MARKING
		FOOT
MILLED PAVEMENT	STA. 968+50.00 TO STA. 980+50.00	120.0
ONE APPLICATION PRIME	STA. 968+50.00 TO STA. 980+50.00	120.0
LIFT BINDER COURSE	STA. 968+50.00 TO STA. 980+50.00	120.0
LIFT SURFACE COURSE	STA. 968+50.00 TO STA. 980+50.00	120.0
TOTAL		480.0

TRAFFIC BARRIER TERMINAL, TYPE 6	
LOCATION	63100085 TRAFFIC BARRIER TERMINAL, TYPE 6
	EACH
STA. 973+37.36 TO STA. 973+81.11, LT	1
STA. 973+37.36 TO STA. 973+81.11, RT	1
STA. 975+70.90 TO STA. 976+14.65, LT	1
STA. 975+70.90 TO STA. 976+14.65, RT	1
TOTAL	4

PERMANENT SURVEY MARKERS, TYPE II	
LOCATION	66700305 PERMANENT SURVEY MARKERS, TYPE II
	EACH
TO BE DETERMINED	1
TOTAL	1

TEMPORARY PAVEMENT MARKING-LINE 4"		
LOCATION		70300220 TEMPORARY PAVEMENT MARKING-LINE 4"
		FOOT
LT EDGE	STA. 968+50.00 TO STA. 980+50.00	1200
RT EDGE	STA. 968+50.00 TO STA. 980+50.00	1200
CENTERLINE	STA. 968+50.00 TO STA. 971+80.00 SKIP-DASH	83
CENTERLINE	STA. 971+80.00 TO STA. 980+50.00 SOLID-DASH	1088
TOTAL		3571

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	
LOCATION	63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT
	EACH
STA. 971+24.86 TO STA. 971+74.86, RT	1
STA. 972+24.85 TO STA. 972+74.85, LT	1
STA. 976+77.15 TO STA. 977+27.15, RT	1
TOTAL	3

BASE COURSE WIDENING REMOVAL				
LOCATION	LENGTH (FT)	WIDTH (FT)	#7000599 BASE COURSE WIDENING REMOVAL SQ YD	
STA. 973+44.50 TO STA. 973+71.92, RT	27.4	5.2	15.8	
STA. 976+40.00 TO STA. 977+81.00, LT	141.0	4.0	62.7	
STA. 977+50.00 TO STA. 977+88.00, RT	38.0	5.4	22.8	
TOTAL			101.3	

WORK ZONE PAVEMENT MARKING REMOVAL				
LOCATION	WIDTH	LENGTH	70301000 WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	
LIFT SURFACE COURSE	4"	120.0	40.0	
TOTAL			40.0	

GUARDRAIL REMOVAL	
LOCATION	63200310 GUARDRAIL REMOVAL
	FOOT
STA. 972+58.87 TO STA. 973+71.57, RT	112.7
STA. 972+83.29 TO STA. 973+71.81, LT	88.6
STA. 975+60.18 TO STA. 976+23.38, LT	63.2
STA. 975+59.88 TO STA. 976+23.46, RT	63.6
TOTAL	328.1

TEMPORARY CONCRETE BARRIER	
LOCATION	70400100 TEMPORARY CONCRETE BARRIER
	FOOT
STA. 971+01.30 TO STA. 977+50.70 (Stage I Construction) (52 Barriers @ 12.5' each = 650')	650
TOTAL	650

RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	70400200 RELOCATE TEMPORARY CONCRETE BARRIER
	FOOT
STA. 971+13.75 TO STA. 977+38.24 (Stage II Construction) (50 Barriers @ 12.5' each = 625')	625
TOTAL	625