

INDEX OF SHEETS

1 COVER SHEET
 2 INDEX OF SHEETS, HIGHWAY STANDARDS,
 GENERAL NOTES & COMMITMENTS
 3-3A SUMMARY OF QUANTITIES
 4 TYPICAL SECTIONS
 5 SCHEDULE OF QUANTITIES
 6-7 PLAN SHEETS
 8-9 STAGE 1 CONSTRUCTION
 10-11 STAGE 2 CONSTRUCTION
 11A-11B PAVEMENT MARKING
 12-20 BRIDGE PLANS
 21-21B DETAILS

GENERAL NOTES:

1. THE STANDARDS AND REVISION LISTED NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMERENIP
 - VILLAGE OF EVANSVILLE
 - NEW WAVE COMMUNICATIONS, INC.
 - VERIZON NORTH, INC.
 MEMBERS OF J.U.L.I.E. (800) 892-0123 OR 811 ARE INDICATED BY AN *. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT EACH END OF THE PROJECT AND ALL INTERSECTING SIDE ROADS AND WILL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE, 48".
5. A QUANTITY OF 1100 FOOT OF "TEMPORARY PAVEMENT MARKING - LINE 6" WHITE HAS BEEN INCLUDED IN THE PLANS FOR PAINTING THE BOTTOM 6" OF THE TEMPORARY CONCRETE BARRIER.
6. TRAFFIC CONTROL AND PROTECTION STANDARD 701201 IS TO PLACE THE INLET AND PIPE CULVERT.
7. THE PROPOSED REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL ITEM FOR THE NORTHWEST QUADRANT OF THE PROJECT SHALL COMPLY WITH THE DETAILS IN THE PLANS AND MANUFACTURER'S DETAILS IN ORDER TO MATCH THE EXISTING GUARDRAIL ELEMENTS THAT WERE ERRECTED PRIOR TO JANUARY 1, 2007.
8. THE COST OF "BARRICADES, TYPE III" USED DURING STAGE CONSTRUCTION SHALL BE INCLUDED IN THE COST OF "TRAFFIC CONTROL AN DPROTECTION, STANDARD 701321 (SPECIAL)".
9. THE CONTRACTOR SHALL PROVIDE TWO SIGNAL HEADS FOR THE SIDE ROAD LOCATED WITHIN THE STAGE CONSTRUCTION AT STA ±786+00. THE SIGNALS, DETECTOR LOOPS, AND THE NUMBER OF TURNS OF WIRE IN THE LOOPS SHALL BE AS DETERMINED BY THE ENGINEER. ALL ADDITIONAL TRAFFIC SIGANL HEADS, LOOP DETECTORS AND ASSOCIATED EQUIPMENT REQUIRED TO MAINTAIN ACCESS AT THE ENTRANCE SHALL BE INCLUDED IN THE COST OF "TEMPORARY BRIDGE TRAFFIC SIGNALS", EACH.

COMMITMENTS

NONE

HIGHWAY STANDARDS

- 000001-05
 001001-02
 602301-02
 604006-04
 630001-08
 630301-05
 631031-07
 635006-03
 635011-02
 701201-03
 701311-03
 701321-10
 701901-01
 704001-05
 780001-02
 781001-03

Rev. Sheet 10-9-09

FILE NAME = #FILEL*	USER NAME = #USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES, AND STANDARDS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = #SCALE*	CHECKED -	REVISED -			312	73-VB-1	RANDOLPH	21	2
PLOT DATE = #DATE*	DATE -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT CONTRACT NO. 76C78		