

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE		CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			100% STATE		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X131-2A			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X131-2A		
2100105	STONE RIPRAP, CLASS A3	38 YD	10	10			63200310	GUARDRAIL REMOVAL	FOOT	225	225		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3			63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	250	250		
40600300	AGGREGATE (PRIME COAT)	TON	2	2			67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	196	196		⚠	67100100	MOBILIZATION	L SUM	1	1		
40600990	TEMPORARY RAMP	SQ YD	36	36			70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	20	20		⚠	70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	50	50			70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	395	395			70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1		
44004250	PAVED SHOULDER REMOVAL	SQ YD	55	55		⚠	70106700	TEMPORARY RUMBLE STRIP	EACH	6	6		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	6	6			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	220	220		⚠
48203100	HOT-MIX ASPHALT SHOULDERS	TON	24	24			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1998	1998		⚠
50102400	CONCRETE REMOVAL	CU YD	13.3	13.3			70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1100	1100		⚠
50157300	PROTECTIVE SHIELD	SQ YD	249	249			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	40	40		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	14.7	14.7			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	779	779		⚠
50300260	BRIDGE DECK GROOVING	SQ YD	675	675			70400100	TEMPORARY CONCRETE BARRIER	FOOT	575	575		
50300300	PROTECTIVE COAT	SQ YD	720	720			70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	525	525		
50300530	FLOOR DRAIN EXTENSION	EACH	12	12			*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1650	1650		⚠
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1530	1530			*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	348	348		⚠
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12			*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10		⚠
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1520	1520			*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2		⚠
50800515	BAR SPLICERS	EACH	24	24			*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	102.5	102.5			*78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6	6			*78200530	BARRIER WALL MARKERS, TYPE C	EACH	2	2		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6	6			*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
52100520	ANCHOR BOLTS, 1"	EACH	24	24			78300100	PAVEMENT MARKING REMOVAL	SO FT	666	666		⚠
54213450	END SECTIONS 15"	EACH	1	1			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	12	12		⚠
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	70	70			X0321468	PLUG EXISTING DECK DRAINS	EACH	16	16		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1			XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SO YD	689	689		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	250	250			Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SO YD	689	689		
60900515	CONCRETE THRUST BLOCKS	EACH	1	1			Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	97	97		
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	163	163			Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2									
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2									

⚠ Rev. 10-9-09

* SPECIALTY ITEMS

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			312	73-VB-1	RANDOLPH	21	3	
PLOT SCALE = #SCALE#		CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.					
PLOT DATE = #DATE#		DATE -	REVISED -			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT					