

TEMPORARY RAMP SCHEDULE				
LOCATION	WIDTH FOOT	LENGTH FOOT	TEMPORARY RAMP	
			SO	YD
STA 780+88.59	32.0	5	18	
STA 784+20.11	32.0	5	18	
TOTAL				36

RESURFACING SCHEDULE											
LOCATION	STATION TO STATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE	HOT-MIX ASPHALT ASPHALT SURFACE COURSE, 1 1/2"	HOT-MIX ASPHALT SHOULDERS	AGGREGATE WEDGE SHOULDER	HOT-MIX ASPHALT SURFACE REMOVAL 1/2"	PAVED SHOULDER REMOVAL	PCC SURFACE REMOVAL - BUTT JOINT	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1/2"
		TON	TON	TON	TON	TON	TON	SO YD	SO YD	SO YD	SO YD
STA 780+88.59 TO STA 781+93.82		0.17	0.79	11.8	29.5	14.4	5.9	236.4		97.8	281
STA 783+47.57 TO STA 784+20.11		0.11	0.51	8.2	20.4	8.7		158.6	17.0	97.8	193
STA 784+20.11 TO STA 785+89.05									38.0		
SUB-TOTAL		0.3	1.3	20.0	49.9	23.1	5.9	395.0	55.0	195.6	474
TOTAL		0.3	2	20	50	24	6	395	55	196	474

GUARDRAIL SCHEDULE									
LOCATION	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL), TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 6	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	GUARDRAIL MARKERS TYPE A	BARRIER WALL MARKERS TYPE B	BARRIER WALL MARKERS TYPE C	TERMINAL MARKERS DIRECT APPLIED
	FOOT	FOOT	EACH	EACH	FOOT	EACH	EACH	EACH	EACH
NB IL 3						4	1	1	
SB IL 3						4	1	1	2
NW QUADRANT					250				
SW QUADRANT	112.5	75	1	1					
SE QUADRANT	112.5	87.5	1	1					
TOTAL	225	162.50	2	2	250	8	2	2	2

PAVEMENT MARKING SCHEDULE															
LOCATION	THERMOPLASTIC PAVEMENT MARKING			POLYUREA PAVEMENT MARKING			PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER 2-WAY AMBER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) 2-WAY AMBER	SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING			WORK ZONE PAVEMENT MARKING REMOVAL
	SKIP-DASH CENTERLINE 4" YELLOW	EDGE LINE 4" WHITE		SKIP-DASH CENTERLINE 4" YELLOW	EDGE LINE 4" WHITE							SKIP-DASH CENTERLINE 4" YELLOW	EDGE LINE 4" WHITE		
		FOOT	FOOT		FOOT	FOOT							FOOT	FOOT	
STA 778+00.00 TO STA 781+93.82	100	394	394				296	5	5		108	100	394	394	332
STA 781+93.82 TO STA 783+47.57				40	154	154	116	2		2	16	40	154	154	121
STA 783+47.57 TO STA 786+88.76	80	341	341				254	5	5		96	80	341	341	286
STOP BARS ON LIBERTY STREET															40
SUB-TOTAL	180	735	735	40	154	154	666	12	10	2	220	220	889	889	
TOTAL		1650		348									1998		779

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -		SCALE:	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	312	73-VB-I	RANDOLPH	21 5
		CHECKED -	REVISED -						CONTRACT NO. 76C78			
		DATE -	REVISED -		FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT							

Rev. Sheet 10-9-09