

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X131-2A			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X131-2A		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3			63200310	GUARDRAIL REMOVAL	FOOT	225	225		
40600300	AGGREGATE (PRIME COAT)	TON	2	2			63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL	FOOT	250	250		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	200	200			67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
40600990	TEMPORARY RAMP	SQ YD	36	36			67100100	MOBILIZATION	L SUM	1	1		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	18	18			70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	50	50			70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		
44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	395	395			70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
44004250	PAVED SHOULDER REMOVAL	SQ YD	17	17			70106600	TEMPORARY BRIDGE TRAFFIC SIGNALS (STATE FURNISHED CONTROLLER)	EACH	1	1		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	6	6			70106700	TEMPORARY RUMBLE STRIP	EACH	6	6		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	24	24			70300100	SHORT-TERM PAVEMENT MARKING	FOOT	198	198		
50102400	CONCRETE REMOVAL	CU YD	13.3	13.3			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1867	1867		
50157300	PROTECTIVE SHIELD	SQ YD	249	249			70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	575	575		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	14.7	14.7			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	40	40		
50300260	BRIDGE DECK GROOVING	SQ YD	675	675			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	729	729		
50300300	PROTECTIVE COAT	SQ YD	720	720			70400100	TEMPORARY CONCRETE BARRIER	FOOT	575	575		
50300530	FLOOR DRAIN EXTENSION	EACH	12	12			70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	525	525		
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1530	1530			*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1520	1520		
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12			*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	347	347		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1520	1520			*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9		
50800515	BAR SPLICERS	EACH	24	24			*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	102.5	102.5			*78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6	6			*78200520	BARRIER WALL MARKERS, TYPE B	EACH	2	2		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6	6			*78200530	BARRIER WALL MARKERS, TYPE C	EACH	2	2		
52100520	ANCHOR BOLTS, 1"	EACH	24	24			*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
54213450	END SECTIONS 15"	EACH	1	1			78300100	PAVEMENT MARKING REMOVAL	SO FT	623	623		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	70	70			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9		
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1			X0321468	PLUG EXISTING DECK DRAINS	EACH	16	16		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	250	250			XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SO YD	689	689		
60900515	CONCRETE THRUST BLOCKS	EACH	1	1			Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SO YD	689	689		
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	163	163			Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	97	97		
*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2			Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2									

**\* SPECIALTY ITEMS**

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.P. RTE. 312	SECTION 73-VB-1	COUNTY RANDOLPH	TOTAL SHEETS 21	SHEET NO. 3
#FILE#		DRAWN -	REVISED -							CONTRACT NO. 76C78			
		CHECKED -	REVISED -							FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			
		DATE -	REVISED -										