

GENERAL NOTES

THE THICKNESS OF THE HOT MIX ASPHALT MIXTURE SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT MIX ASPHALT MIXTURE IS PLACED.

FACTORS USED FOR QUANTITY CALCULATIONS ARE AS FOLLOWS:

ALL HOT MIX ASPHALT:	2.016 TONS/CU. YD.
HOT MIX ASPHALT MATERIALS ON PAVEMENT:	0.09 GAL./SQ. YD.
AGGREGATE (PRIME COAT):	0.0015 TONS/SQ. YD.
ALL AGGREGATE:	2.05 TONS/CU. YD.
RIPRAP	1.50 TONS/CU YD

PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING STRUCTURE HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF THE WORK. THE CONTRACTOR, HOWEVER, WILL BE PAID FOR THE ACTUAL QUANTITY FURNISHED AT THE UNIT PRICE BID FOR THE WORK. CONSTRUCTION PLANS ARE AVAILABLE FOR REVIEW AT THE DISTRICT 9 OFFICE.

IN ADDITION TO THE REQUIREMENTS OF ARTICLE 107.16 THE CONTRACTOR SHALL PROTECT THE SURFACE OF ALL BRIDGE DECK AND BRIDGE APPROACH PAVEMENTS IN A MANNER SATISFACTORY TO THE ENGINEER BEFORE ANY EQUIPMENT IS ALLOWED TO CROSS THE STRUCTURE. PROTECTION SHALL BE PROVIDED FOR ALL EQUIPMENT AS DEFINED IN ARTICLE 101.17 REGARDLESS IF TRACK MOUNTED OR WHEELED.

AT ALL LOCATIONS WHERE HOT MIX ASPHALT OR CONCRETE PAVEMENT JOINS AN EXISTING HOT MIX ASPHALT OR CONCRETE PAVEMENT, A SAWED JOINT SHALL BE CONSTRUCTED. THE COST OF THIS JOINT SHALL BE INCLUDED IN THE TYPE OF PAVEMENT BEING CONSTRUCTED.

QUANTITIES SHOWN IN THE PLANS FOR BRIDGE DECK GROOVING AND PROTECTIVE COAT INCLUDE THE BRIDGE, THE BRIDGE APPROACH PAVEMENTS, AND THE BRIDGE APPROACH PAVEMENT CONNECTORS (PCC).

PROTECTIVE COAT SHALL BE APPLIED TO THE BRIDGE, THE BRIDGE APPROACH PAVEMENTS, AND THE BRIDGE APPROACH PAVEMENT CONNECTORS (PCC) IN ACCORDANCE WITH ARTICLE 503.19 OF THE STANDARD SPECIFICATIONS. THE PROTECTIVE COAT SHALL BE APPLIED REGARDLESS OF THE CURING METHOD USED. THE RATE OF APPLICATION FOR EACH COAT ON SAW CUT GROOVED AREAS SHALL BE 25 SQUARE YARDS PER GALLON OF MIXTURE.

REMOVAL OF EXISTING 13" THICK BRIDGE APPROACH PAVEMENTS ARE INCLUDED IN THE QUANTITY FOR PAVEMENT REMOVAL - 116 SQ YD.

TREES SHALL BE PRESERVED THROUGHOUT THIS SECTION AS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER. GENERALLY, TREES OUTSIDE THE CONSTRUCTION LIMITS, AND WHICH DO NOT INTERFERE WITH CONSTRUCTION, SHALL NOT BE DISTURBED.

IT WILL BE THE CONTRACTOR'S RESPONSIBILITY TO REMOVE ANY DEBRIS OR DIRT CAUSED BY CONSTRUCTION ACTIVITY THAT COVERS THE NEW RIPRAP AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE LEFT IN PLACE UNTIL REMOVAL IS REQUIRED TO CONSTRUCT FINAL GRADE LINES.

THE QUANTITY OF SHORT TERM PAVEMENT MARKING SHOWN IN THE PLANS IS BASED ON ONE APPLICATION EACH FOR THE BINDER COURSE AND THE SURFACE COURSE.

THE QUANTITY OF TEMPORARY PAVEMENT MARKING SHOWN IN THE PLANS IS BASED ON ONE APPLICATION FOR THE SURFACE COURSE.

PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS THE RESIDENT ENGINEER SHOULD CONTACT THE BUREAU OF OPERATIONS AND ARRANGE FOR INSPECTION AND APPROVAL OF THE PAVEMENT MARKING LAYOUT.

COST OF REMOVING HOT MIX ASPHALT BASE COURSE WIDENING, 10" USED FOR STAGE I TRAFFIC IS INCLUDED IN "PAVED SHOULDER REMOVAL-SQ YD."

THE ADVANCE DETECTOR LOOPS ARE TYPICALLY LOCATED 275 FEET IN ADVANCE OF THE STOP BAR. THE BUREAU OF OPERATIONS SHOULD APPROVE THE LOOP LOCATIONS PRIOR TO INSTALLATION.

THE CENTERLINE PAVEMENT MARKING SHOULD BE REMOVED FROM THE STOP BAR TO THE SAND ATTENUATORS OR DRUMS. EDGE LINE PAVEMENT MARKING SHOULD BE REMOVED IF A 10 FOOT LANE WIDTH CANNOT BE MAINTAINED. TEMPORARY EDGE LINES SHOULD BE INSTALLED WHEN THE EDGE LINES ARE REMOVED.

THE BARRIER WALL AND GUARDRAIL REFLECTORS AS SHOWN ON STANDARD 701321 SHALL BE INSTALLED PRIOR TO OPENING TO TRAFFIC.

ANY TIME THE CONCRETE BARRIER IS NOT IN THE PROPER POSITION, FLAGGERS SHALL BE IN PLACE TO CONTROL TRAFFIC. THE TEMPORARY TRAFFIC SIGNALS SHALL BE SET TO FLASH ALL RED.

TRIM EDGES OF EXISTING HOT MIX ASPHALT SURFACE FLUSH WITH EXISTING PAVEMENT PRIOR TO CONSTRUCTING NEW BASE COURSE WIDENING.

THE HOT MIX ASPHALT BASE COURSE WIDENING, 10" CONSTRUCTED IN PRE-STAGE 1 MAY BE INCORPORATED INTO THE FINAL HOT MIX ASPHALT SHOULDERS, 8" DURING STAGE II CONSTRUCTION IF APPROVED BY THE ENGINEER. SUCH CHANGE WILL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION, BUT THE CONTRACTOR WILL BE PAID FOR THE ACTUAL QUANTITY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

COMMITMENTS: NONE AS OF JUNE 26, 2009, REFER TO COMMITMENT FILE FOR ANY COMMITMENTS AFTER THIS DATE.

HIGHWAY STANDARDS

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
280001-04	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
420401-07	BRIDGE APPROACH PAVEMENT
421001-02	REINFORCEMENT FOR CONTINUOUSLY REINFORCED PCC PAVEMENT
482006-03	HOT-MIX ASPHALT SHOULDER ADJACENT TO RIGID PAVEMENT
515001-03	NAME PLATE FOR BRIDGES
630001-08	STEEL PLATE BEAM GUARDRAIL
630201-06	PCC/BITUMINOUS STABILIZATION AT STEEL PLATE BEAM GUARDRAIL
630301-05	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631031-07	TRAFFIC BARRIER TERMINAL, TYPE 6
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER & MOUNTING DETAILS
701006-03	OFF-ROAD OPERATIONS, 2L 2W, 4.5 m (15') TO 600 mm (24") AWAY, FOR SPEEDS ≥ 45 MPH
701201-03	LANE CLOSURE, 2L 2W, DAY ONLY, ON-ROAD TO 600 mm (24") OFF-ROAD, FOR SPEEDS ≥ 45 MPH
701301-03	LANE CLOSURE, 2L 2W, SHORT TIME OPERATIONS, FOR SPEEDS ≥ 45 MPH
701321-10	LANE CLOSURE, 2L, 2W, BRIDGE REPAIR WITH BARRIER
701326-03	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING, FOR SPEEDS ≥ 45 MPH
701901-01	TRAFFIC CONTROL DEVICES
704001-05	TEMPORARY CONCRETE BARRIER
780001-02	TYPICAL PAVEMENT MARKINGS
BLR21-8	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES FOR CONSTRUCTION ON RURAL LOCAL ROADS

601101-01

INDEX OF SHEETS

1	COVER SHEET
2	GENERAL NOTES; HIGHWAY STANDARDS; INDEX OF SHEETS
3-4	SUMMARY OF QUANTITIES
5	TYPICAL SECTION; MIXTURE REQUIREMENTS
6-7	SCHEDULES OF QUANTITIES
8	PLAN & PROFILE SHEET
9	ROW SHEET
10	STAGE CONSTRUCTION PLAN
11	DETOUR SIGNING AND ROAD CLOSURE
12	HOT-MIX ASPHALT SHOULDER AND GUARDRAIL PLAN
13	EROSION CONTROL PLAN
14	DETAILS- BUTT JOINT, SEEDING & MULCHING STEP CONSTRUCTION ON EXISTING FILL
15-16	DETAILS- BRIDGE APPROACH PAVEMENT
17-22	CROSS SECTIONS
*23-47	STRUCTURE PLANS

* 35-37 NOT USED

Rev 10-20-09

Rev

Prepared By:	<i>Dani Hillman</i> DISTRICT STUDIES & PLANS ENGINEER
Examined By:	<i>James Travis Emery</i> DISTRICT LAND ACQUISITION ENGINEER
Examined By:	<i>Conni Nelson</i> DISTRICT PROGRAM DEVELOPMENT ENGINEER
Examined By:	<i>Scott Wiley</i> DISTRICT OPERATIONS ENGINEER
Examined By:	<i>Jim Swathlow</i> DISTRICT CONSTRUCTION ENGINEER
Examined By:	<i>[Signature]</i> DISTRICT MATERIALS ENGINEER
Examined By:	<i>Jim Swathlow</i> DISTRICT PROJECT IMPLEMENTATION ENGINEER
Examined By:	<i>[Signature]</i> ASSISTANT REGIONAL ENGINEER
Approved By:	<i>Mary C. Ramic</i> DEPUTY DIRECTOR OF HIGHWAYS, REGION ENGINEER
DATE	June 22 2009

FILE NAME =	USER NAME = halsteadtw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, HIGHWAY STANDARDS AND INDEX OF SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw_work\PWIDOT\HALSTEADTW\dms49780	978064_sht_misc.dgn	DRAWN -	REVISED -			865	16B-2	PERRY	47	2	
	PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.					
	PLOT DATE = 6/8/2009	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					