


CONSTRUCTION LAYOUT	
LOCATION	Z0013798 CONSTRUCTION LAYOUT
	L SUM
ENTIRE PROJECT	1
TOTAL	1

PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 18"			
LOCATION	OFFSET	LT/RT	54207783 PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM, EQUIVALENT ROUND-SIZE 18"
	FEET		FOOT
STA. 206+14.00 TO STA. 206+66.00, ENTRANCE	33.0' TO 32.4'	LT	52
TOTAL			62

AGGREGATE BASE COURSE, TYPE B							
LOCATION	REQUIRED THICKNESS WEST SIDE	REQUIRED THICKNESS EAST SIDE	WIDTH (2' AVERAGE WIDTH - EACH SIDE)	LENGTH	DEPTH	VOLUME	35101400 AGGREGATE BASE COURSE, TYPE B
	INCHES	INCHES	FEET	FEET	INCH	CU YD	TON
FOR ADDITIONAL PAVEMENT THICKNESS							
STA. 128+75.00	6	3				67.4	138
STA. 130+78.50	5.5	3.5				200	410
STA. 139+78.50	1.5	1.5				116.7	239
STA. 148+78.50	4	0				83.3	171
STA. 157+78.50	1	0				16.7	34
STA. 166+78.50	0	0				0	0
STA. 175+78.50	0	0				0	0
STA. 184+78.50	0	0				50	103
STA. 193+78.50	2	1				83.3	171
STA. 202+78.50	0.5	1.5				41.7	85
STA. 211+78.50	0	0.5				54.2	111
STA. 220+78.50	0.5	2.25				187.5	384
STA. 229+78.50	8	0.5				209.5	417
STA. 236+25.00	8	0.5					
FOR EARTH EX. WIDENING LOCATIONS (2' AVERAGE WIDTH EACH SIDE OF EXIST. EDGE OF PAVEMENT)							
STA. 128+75 TO STA. 130+00			4	125	9	13.9	28.5
STA. 130+00 TO STA. 140+00			4	1000	9	111.1	227.8
STA. 140+00 TO STA. 150+00			4	1000	9	111.1	227.8
STA. 150+00 TO STA. 160+00			4	1000	9	111.1	227.8
STA. 160+00 TO STA. 170+00			4	1000	9	111.1	227.8
STA. 170+00 TO STA. 180+00			4	1000	9	111.1	227.8
STA. 180+00 TO STA. 190+00			4	1000	9	111.1	227.8
STA. 190+00 TO STA. 200+00			4	1000	9	111.1	227.8
STA. 200+00 TO STA. 210+00			4	1000	9	111.1	227.8
STA. 210+00 TO STA. 220+00			4	1000	9	111.1	227.8
STA. 220+00 TO STA. 230+00			4	1000	9	111.1	227.8
STA. 230+00 TO STA. 235+00			4	500	9	55.6	113.9
STA. 235+00 TO STA. 236+25			4	125	9	13.9	28.5
TOTALS						4,712	

Revised 10-22-09



FILE NAME =	USER NAME = #USERS	DESIGNED -	REVISED -
S:\237\2008\23708011\Fulton CH 6 N-S\CAVADO\CADD Sheets\0406011\sh-t-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 2,0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/15/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
145B	03-00125-02-RS	FULTON	66	8
CONTRACT NO. 89415				
SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.

FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT
---------------------	---------------------------