

SCHEDULE OF QUANTITIES

CONSTRUCTION LAYOUT	
LOCATION	L. SUM
ENTIRE PROJECT	1
TOTAL	1

RELOCATE SIGN PANEL AND POST		
LOCATION		EACH
STA. 107+00	RT	1
STA. 114+33	LT	1
TOTAL		2

STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A				
LOCATION				FOOT
STA. 101+40.00	TO	STA. 115+15.00	LT	1,375
TOTAL				1,375

FILLING EXISTING CULVERTS				
LOCATION				EACH
STA. 109+26.00	TO	STA. 110+43.00	LT	1
TOTAL				1

AGGREGATE FOR TEMPORARY ACCESS	
LOCATION	TON
ENTIRE PROJECT	10
TOTAL	10

TEMPORARY RAMP	
LOCATION	SQ YD
STA. 101+40	13
STA. 5+14	13
STA. 6+88	13
STA. 115+15	13
TOTAL	52

ROAD PAVING SCHEDULE										
LOCATION		SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	HOT-MIX ASPHALT BASE COURSE, 9"	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	HMA SURFACE COURSE MIX D, N50	AGGREGATE SHOULDERS, TYPE B 8"	HOT-MIX ASPHALT SHOULDERS, 8"
LOCATION		SQ YD	SQ YD	SQ YD	SQ YD	TON	GALLON	TON	SQ YD	SQ YD
IL. ROUTE 9										
STA. 101+40.00	TO	STA. 115+15.00				10	833	341.6	324.7	
STA. 101+40.00	TO	STA. 108+82.60								
STA. 101+40.00	TO	STA. 6+26.0 (ACCESS ROAD)								385.6
STA. 101+55.00	TO	STA. 114+90.00	1,533.0		1,533.0			128.7		
STA. 108+45.30	TO	STA. 110+47.10 (ACCESS ROAD)	707.0		707.0					
STA. 114+32.30	TO	STA. 115+15.00							17.2	
ACCESS ROAD										
STA. 5+24.40	TO	STA. 6+00.00						59.4		
STA. 6+00.00	TO	STA. 6+88.00						23.0		
STA. 6+26.00	TO	STA. 115+15.0 (IL. ROUTE 9)								256.0
TOTAL		707.0	1,533.0	707.0	1,533.0	10	833	552.7	341.9	641.6

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
X:\PROJECTS\60098651\DCN\PLANS-XREFS\08-SCHED QTY.DGN		DRAWN -	REVISED -
	PLOT SCALE =	CHECKED -	REVISED -
	PLOT DATE = 08-18-09	DATE - 08-18-09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

TAZEWELL COUNTY ACCESS ROAD\ILLINOIS ROUTE 9			
SCHEDULE OF QUANTITIES			
SCALE: NONE	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	06-00000-00-FP	TAZEWELL	42	8
CONTRACT NO. 89531				
ILLINOIS FED. AID PROJECT				