

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
367	01-00100-00-RS	WOODFORD	5	2
STA.		TO STA.		
FED. ROAD DIST. NO. 4		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

ITEM #	DESCRIPTION	UNIT	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3,602
40600895	CONSTRUCT TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SO YD	378
40600990	TEMPORARY RAMP	SO YD	80
40603510	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX 'C', N50	TON	4,105
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	225
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SO YD	43,273
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	1,993
* 44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	66
* 48101800	AGGREGATE SHOULDERS (SPECIAL)	SO YD	18,092
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,657
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	552
78001100	PAINT PAVEMENT MARKING-LINE 4"	FOOT	46,112
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	208
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	165

* SEE SPECIAL PROVISIONS

△ SPECIALTY ITEMS

ENTRANCE #	TYPE	STATION	WIDTH (FT)	SURFACE	40800050 INCIDENTAL SURFACING (TONS)	40603510 POLYMERIZED HMA SURFACE COURSE MIX 'C', N50 (TONS)
1	FIELD ENTRANCE	N/A 1100N	30	ASPH	2	N/A
2	PRIVATE ENTRANCE	2+50 R	30	ASPH	2.7	N/A
3	FIELD ENTRANCE	15+26 L	30	ASPH	1.5	N/A
4	FIELD ENTRANCE	15+50 R	30	ASPH	1.5	N/A
5	FIELD ENTRANCE	29+56 R	30	AGG	1.5	N/A
6	FIELD ENTRANCE	29+73 L	30	ASPH	1.5	N/A
7	FIELD ENTRANCE	34+95 R	30	ASPH	1.5	N/A
8	FIELD ENTRANCE	45+71 L	30	ASPH	1.5	N/A
9	PRIVATE ENTRANCE	45+71R	30	ASPH	2.7	N/A
10	FIELD ENTRANCE	61+88 R	30	ASPH	1.5	N/A
11	PRIVATE ENTRANCE	68+74 R	30	ASPH	3.1	N/A
12	FIELD ENTRANCE	68+78 L	30	ASPH	1.5	N/A
13	FIELD ENTRANCE	72+58 R	30	ASPH	1.5	N/A
14	FIELD ENTRANCE	79+16 L	30	ASPH	1.5	N/A
15	FIELD ENTRANCE	86+15 L	35	ASPH	1.6	N/A
16	FIELD ENTRANCE	86+30 R	35	ASPH	1.6	N/A
17	PRIVATE ENTRANCE	106+37 R	60	ASPH	2.7	N/A
18	FIELD ENTRANCE	106+43 L	40	ASPH	1.9	N/A
19	FIELD ENTRANCE	108+94 L	40	ASPH	1.6	N/A
20	FIELD ENTRANCE	114+46 L	30	ASPH	1.5	N/A
21	FIELD ENTRANCE	114+74 R	30	ASPH	1.5	N/A
22	PRIVATE ENTRANCE	117+00 L	30	ASPH	3.1	N/A
23	FIELD ENTRANCE	131+62 L	30	ASPH	1.5	N/A
24	PRIVATE ENTRANCE	132+85 L	24	ASPH	2.1	N/A
25	PRIVATE ENTRANCE	134+50 L	30	ASPH	3	N/A
26	PRIVATE ENTRANCE	136+33 L	30	ASPH	3	N/A
27	FIELD ENTRANCE	142+93 L	30	ASPH	1.5	N/A
28	FIELD ENTRANCE	143+00 R	30	ASPH	1.5	N/A
29	PRIVATE ENTRANCE	146+00 R	45	AGG	5.34	N/A
30	PRIVATE ENTRANCE	149+41R	80	ASPH	9.9	N/A
31	FIELD ENTRANCE	149+49 L	30	ASPH	1.5	N/A
32	PRIVATE ENTRANCE	154+85 L	45	ASPH	4.31	N/A
33	PRIVATE ENTRANCE	157+53 L	35	CONC	4	N/A
34	PRIVATE ENTRANCE	158+73 L	30	ASPH	2.6	N/A
35	PRIVATE ENTRANCE	160+26 L	55	ASPH	6.2	N/A
36	PRIVATE ENTRANCE	161+65 L	30	CONC	2.9	N/A
37	PRIVATE ENTRANCE	162+19 L	35	ASPH	3.2	N/A
	MAIN LINE	0+00 - 165+69	24	N/A	N/A	4,103.8
	MAILBOX TURNOUTS 12 @ 2 TONS EACH =				24	N/A
	SIDE ROADS (SEE TABLE)				103	N/A
					TOTAL	220.5
					USE	225
						4,105

STATION TO STATION	78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)	70300100 SHORT-TERM PAVEMENT MARKINGS (FOOT)	70301000 WORK ZONE PAVEMENT MARKING REMOVAL (SO FT)	78100100 RAISED REFLECTIVE PAVEMENT MARKER (EACH)
0+00 - 165+69	165	1,657	552	208

SIDE ROAD	STATION	LENGTH (FT)	40800050 INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)
			40600100 BITUMINOUS MATERIALS (PRIME COAT) GALLONS
1100 N. LEFT	00+68	60	30
1100 N. RIGHT	00+84	60	28
1200 N. LEFT	57+84	30	13
1200 N. RIGHT	57+87	30	10
PRAIRIE HILLS SUB. LEFT	138+70	30	10
W. LOCUST ST. RIGHT	161+43	22	12
		TOTAL	103 TONS


STATION TO STATION	40600100 BITUMINOUS MATERIALS (PRIME COAT) GALLONS
0+00 - 165+69	3,414
FIELD/PRIVATE ENTRANCES	81
MAILBOX TURNOUTS	19
SIDEROADS	88
TOTAL	3,602

STATION - STATION	48101800 AGGREGATE SHOULDERS (SPECIAL) (SY)
0+20 - 163+03	18,092

	STATION	BITUMINOUS SURFACE REMOVAL (SO YD)	40600990 TEMPORARY RAMP (SO YD)
44000153			
HOT-MIX ASPHALT SURFACE REMOVAL-1"	00+20 - 162+82	43,273	
44000155			
HOT-MIX ASPHALT SURFACE REMOVAL - 1 1/2"	163+03 - 165+69	1,993	
44000198			
HOT-MIX ASPHALT SURFACE REMOVAL-VARIABLE DEPTH	162+82 - 163+03	66	
40600982			
HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	00+00 - 00+20	89	10
	1100N	52	10
	1200N	52	10
	PRARIE HILLS	22	10
	W. LOCUST	47	10
	3 P.E.	116	30
	BUTT JOINT TOTAL=	378 SY	80 SY
	TOTAL=		

	78001100 PAINT PAVEMENT MARKING LINE-4" (FOOT)
YELLOW	13,376
WHITE	32,736
TOTAL	46,112

DATE: 8/06/09
SCALE: 1"=40'
DRAWN BY: BJB
CHECKED BY: DOB



WOODFORD COUNTY
HIGHWAY DEPARTMENT
DENNIS BACHMAN, P.E., COUNTY ENGINEER
301 S. Main St.
Roanoke, IL 61561
TEL: 309-923-2891
FAX: 309-923-7928

F.A.S. RTE. 367
SECTION 01-00100-00-RS
DOUGLAS ROAD
SCHEDULE OF QUANTITIES

SCALE: DATE: 8/06/09
DRAWN BY: BJB
CHECKED BY: DOB