

X028-2A					
CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 3000-2A	STRUCTURE 057-7834
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30	30	
20200100	EARTH EXCAVATION	CU YD	1149	1149	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	300		300
20700220	POROUS GRANULAR EMBANKMENT	CU YD	723		723
* 20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	300		300
20800150	TRENCH BACKFILL	CU YD	230	230	
* 20800250	TRENCH BACKFILL, SPECIAL	CU YD	70	70	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	300	300	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	60	60	
25000110	SEEDING, CLASS 1A	ACRE	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18	
25100115	MULCH, METHOD 2	ACRE	0.2	0.2	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	150	
28000400	PERIMETER EROSION BARRIER	FOOT	230	230	
28000500	INLET AND PIPE PROTECTION	EACH	18	18	
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	1650	1650	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	170	170	
40600990	TEMPORARY RAMP	SU YD	170	170	
40800010	BITUMINOUS MATERIAL (PRIME COAT)	GAL	20	20	
40800050	INCIDENTAL HOT -MIX ASPHALT SURFACING	TON	25	25	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	45	45	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	3450	3450	

* SEE SPECIAL PROVISIONS

X028-2A					
CODE NUMBER	ITEM	UNIT	TOTAL	ROADWAY 3000-2A	STRUCTURE 057-7834
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	210	210	
42400800	DETECTABLE WARNINGS	SQ FT	130	130	
44000100	PAVEMENT REMOVAL	SQ YD	1590	1590	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	210	210	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1120	1120	
44000600	SIDEWALK REMOVAL	SQ FT	3750	3750	
44004000	PAVED DITCH REMOVAL	FOOT	157		157
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	77.1		77.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	172.1		172.1
50300260	BRIDGE DECK GROOVING	SQ YD	494		494
50300300	PROTECTIVE COAT	SQ YD	801		801
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1680		1680
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	152,370		152,370
50800515	BAR SPLICERS	EACH	132		132
50900805	PEDESTRIAN RAILING	FOOT	118		118
50901720	BICYCLE RAILING	FOOT	120		120
* 51100300	SLOPE WALL 6 INCH	SQ YD	437		437
* 51205200	TEMPORARY SHEET PILING	SQ FT	2860		2860
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	366.4		366.4
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	185	185	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	135	135	
55100300	STORM SEWER REMOVAL 8"	FOOT	50	50	
55100500	STORM SEWER REMOVAL 12"	FOOT	-60	60	

* SEE SPECIAL PROVISIONS

DESIGNED - JDA	REVISED -
DRAWN - DRR	REVISED -
CHECKED - PJM	REVISED -
DATE - 07/22/09	REVISED -

TOWN OF NORMAL

SUMMARY OF QUANTITIES

VIRGINIA AVENUE OVER SUGAR CREEK
SECTION 04-00226-00-BR
MCLEAN, COUNTY

F.A.J.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6356	04-00226-00-BR	MCLEAN	52	3
S.N. 057-7834		CONTRACT NO. 91416		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

FARNSWORTH GROUP, INC.

CONSULTING ENGINEERS - 2709 MCGRAW DRIVE BLOOMINGTON, ILLINOIS 61704 (309) 663-8435 / (309) 663-1571 FAX