

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
20200100	EARTH EXCAVATION	CU YD	1000
20400800	FURNISHED EXCAVATION	CU YD	1140
20800150	TRENCH BACKFILL	CU YD	11
21400100	GRADING AND SHAPING DITCHES	FOOT	3300
25001020	SEEDING, CLASS 2A (SPECIAL)	ACRE	4.0
25100630	EROSION CONTROL BLANKET	SQ YD	175
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	400
28000300	TEMPORARY DITCH CHECKS	EACH	9
28000400	PERIMETER EROSION BARRIER	FOOT	665
28000500	INLET AND PIPE PROTECTION	EACH	19
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	72
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1212
35101400	AGGREGATE BASE COURSE, TYPE B	TON	15
35650100	BASE COURSE WIDENING 6"	SQ YD	465
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	87
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	30
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1550
40600300	AGGREGATE (PRIME COAT)	TON	34
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	132
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1710
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	71
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	130
44000100	PAVEMENT REMOVAL	SQ YD	18
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	105
44000400	GUTTER REMOVAL	FOOT	1415
48101200	AGGREGATE SHOULDERS, TYPE B	TON	170
50104400	CONCRETE HEADWALL REMOVAL	EACH	4
50105220	PIPE CULVERT REMOVAL	FOOT	738
50800105	REINFORCEMENT BARS	POUND	30
54002070	EXPANSION BOLTS 3/4 INCH X 15 INCH	EACH	8
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	17
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	1100
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	405
542D5473	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	375
54213450	END SECTIONS 15"	EACH	11

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
54213453	END SECTIONS 18"	EACH	5
54214293	END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2
54248510	CONCRETE COLLAR	CU YD	0.5
60100925	PIPE DRAINS 8"	FOOT	20
60100935	PIPE DRAINS 10"	FOOT	20
60100945	PIPE DRAINS 12"	FOOT	20
60107600	PIPE UNDERDRAINS 4"	FOOT	160
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	3
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	20.0
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	1360
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	60
61100605	MISCELLANEOUS CONCRETE	CU YD	2
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4
61139900	STORM SEWERS, SPECIAL 6"	FOOT	30
61140000	STORM SEWERS, SPECIAL 8"	FOOT	30
61140100	STORM SEWERS, SPECIAL 10"	FOOT	30
61140200	STORM SEWERS, SPECIAL 12"	FOOT	30
63200310	GUARDRAIL REMOVAL	FOOT	420
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	760
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	16065
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	71
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0014700	CULVERT TO BE CLEANED	EACH	5
Z0023600	FILLING EXISTING CULVERTS	EACH	1

* SPECIALTY ITEMS

CONTRACT NO. 91421				
RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	PIATT	53	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 08-00115-01-RS				
** FAS 535				

ESCA
CONSULTANTS, INC.

DESIGNED BY:	ELH	01/09
DRAWN BY:	cj/HAS	01/09
CHECKED BY:	ELH	07/09
APPROVED BY:	RDP	07/09

SUMMARY OF QUANTITIES
FAS 535 (SHADY REST ROAD)
SECTION 08-00115-01-RS
PIATT COUNTY