

CULVERT REMOVAL SCHEDULE		
LOCATION	PIPE CULVERT REMOVAL (50105220)	CONCRETE HEADWALL REMOVAL (50104400)
	FOOT	EACH
STA. 9+12 RT	20	
STA. 12+38 RT	38	
STA. 14+14 RT	44	
STA. 16+78 TO 20+96 RT	420	2
STA. 18+53 LT	38	
STA. 21+48 LT	34	
STA. 26+41 LT	28	
STA. 27+23 RT	25	
STA. 63+83 RT	31	
STA. 73+90 LT	23	
STA. 76+94 LT	37	
STA. 77+96		2
TOTALS	738	4

EARTHWORK SCHEDULE					
LOCATION	EARTH EXCAVATION (20200100)	INCIDENTAL EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT (NOT A PAY ITEM)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-)
	CU YD	CU YD	CU YD	CU YD	CU YD
STA. 8+17 TO 28+40, RT SIDE CUTS & FILLS	18		13	213	-200
STA. 8+17 TO 28+40, LT SIDE CUTS & FILLS	60		45	46	-1
STA. 48+60 TO 84+55, RT SIDE CUTS & FILLS	344		255	24	+231
STA. 48+60 TO 84+55, LT SIDE CUTS & FILLS	578		430	1614	-1184
RIPRAP		15	11		+11
TOTALS	1000	15	754	1897	-1143

EXCAVATION USED AS EMBANKMENT = (EARTH EXCAVATION+INCIDENTAL EXCAVATION)*0.75
 SCHEDULE DOES NOT INCLUDE EARTHWORK AT GRADING AND SHAPING DITCHES LOCATIONS

PAVEMENT MARKING SCHEDULE			
LOCATION	DESCRIPTION	SHORT-TERM PAVEMENT PARKING (70300100)	PAINT PVMT MKG-LINE 4" (78001110)
		FOOT	FOOT
STA. 8+17	DOUBLE YELLOW	405	4050
STA. 28+40	NO PASS LINE		
STA. 8+17 TO	SOLID WHITE		4050
STA. 28+40	EDGE LINE		
STA. 48+60 TO	YELLOW SKIP-DASH	355	885
STA. 84+00	CENTERLINE		
STA. 48+60 TO	SOLID WHITE		7080
STA. 84+00	EDGE LINE		
TOTALS		760	16065

FIELD TILE DRAINAGE SCHEDULE			
LOCATION	ITEM	UNIT	QUANTITY
TO BE USED	MISCELLANEOUS CONCRETE (61100605)	CU YD	2
IN THE FIELD	FIELD TILE JUNCTION VAULTS, 2' DIA. (61133100)	EACH	4
AS DIRECTED	PIPE DRAINS 8" (60100925)	FOOT	20
BY THE ENGINEER	PIPE DRAINS 10" (60100935)	FOOT	20
	PIPE DRAINS 12" (60100945)	FOOT	20
	STORM SEWERS, SPECIAL, 6" (61139900)	FOOT	30
	STORM SEWERS, SPECIAL, 8" (61140000)	FOOT	30
	STORM SEWERS, SPECIAL, 10" (61140100)	FOOT	30
	STORM SEWERS, SPECIAL, 12" (61140200)	FOOT	30
	EXPLORATION TRENCH 52" DEPTH (61100500)	FOOT	60

RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	PIATT	53	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 08-00115-01-RS				
** FAS 535				

ESCA
 CONSULTANTS, INC.

DESIGNED BY:	ELH	01/09
DRAWN BY:	cj/ HAS	01/09
CHECKED BY:	ELH	07/09
APPROVED BY:	RDP	07/09

SCHEDULES OF QUANTITIES
 FAS 535 (SHADY REST ROAD)
 SECTION 08-00115-01-RS
 PIATT COUNTY