SCHEDULE OF QUANTITIES

INLET AND PIPE PROTECTION			
Coles Street			
Station		Offset	EACH
10+32.61	Lt	19.0'	1
10+39.06	Rt	17.6'	1
11+78.78	Lt	18.0'	1
14+36.87	Rt	17.7'	1
14+37.34	Lt	17.8'	1
15+54.66	Lt	18.0'	1
17+02.82	Lt	18.0'	1
18+23.35	Rt	18.0'	1
18+36.61	Lt	18.0'	1
		Total	9

PAVEMENT REMOVAL			
Coles Street			
Sta		Sta	SQ YD
10+16.25	to	22+07.00	4490
		Total	4490

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH			
Coles Street			
Sta		Sta	SQ FT
21+50.00	to	22+07.00	257
		Total	257

PROTECTIVE COAT		
Coles Street		SQ YD
PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)		4490
COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT		35
PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH		29
	Total	4554

SUB-BASE GRANULAR MATERIAL, TYPE A 4"			
Coles Street			
Sta		Sta	SQ YD
10+16.25	to	22+07.00	4490
		Total	4490

PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)			
Coles Street			
Sta		Sta	SQ YD
10+16.25	to	22+07.00	4490
		Total	4490

WATER VALVES TO BE ADJUSTED			
Coles Street			
Station		Offset	EACH
10+18.45	Rt	5.8'	1
17+67.18	Lt	2.5'	1
18+85.72	Rt	13.4'	1
		Total	3

MANHOLES TO BE ADJUSTED			
Coles Street			
Station		Offset	EACH
10+15.92	Lt	1.0'	1
14+36.39	Rt	0.7'	1
18+36.05	Rt	3.3'	1
		Total	3

PAINT PAVEMENT MARKING - LINE 4"			
Coles Street			
Sta		Sta	FOOT
10+16.25	to	22+07.00	298
		Total	298

PAINT PAVEMENT MARKING - LINE 12"		
Coles Street		FOOT
Sta		
10+30.00		20
	Total	20

COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT			
Coles Street			FOOT
Sta		Sta	
21+50.00	to	22+07.00	57
Estimate of Curb Replacement			100
		Total	157

HURST-ROSCHE ENGINEERS, INC.
HILLSBORO, ILLINOIS 62049
(217)532-3959 FAX (217)532-3212