

* 04-00101-00-PV
CONTRACT: 95604

Description: TREE REMOVAL (6 to 15 UNITS DIAMETER)						Unit: UNIT DIAMETER	
Location	Station	Offset (FT)	Side	Quantity (Unit Diameter)			
				Subtotal	Cummulative		
Blohm Ave							
	14+95.3	+3.4	LT	10.0	10.0		
	15+00.8	+5.7	LT	10.0	20.0		
	15+22.9	+9.7	RT	8.0	28.0		
	15+73.0	+6.2	RT	6.0	34.0		
	15+86.4	+3.5	RT	12.0	46.0		
	16+02.8	+2.9	RT	10.0	56.0		
	16+15.4	+1.6	RT	10.0	66.0		
	16+67.6	+4.1	LT	15.0	81.0		
	16+92.5	+6.5	LT	8.0	89.0		
	17+23.8	+9.	LT	10.0	99.0		
Veterans Dr							
	102+83.4	+21.9	LT	10.0	109.0		

Description: TREE REMOVAL (OVER 15 UNITS DIAMETER)						Unit: UNIT DIAMETER	
Location	Station	Offset (FT)	Side	Quantity (Unit Diameter)			
				Subtotal	Cummulative		
Veterans Dr	101+49.2	+22.2	LT	18.0	18.0		

Description: TRENCH BACKFILL										Unit: CUBIC YARD	
Location	Begin		End		Length (FT)	Width (FT)	Area (SF)	Depth (FT)	Quantity (CY)		
	Station	Side	Station	Side					Subtotal	Cumm.	
Blohm Ave											
	9+60.3	LT	10+06.0	LT					15.7	15.7	
	10+06.0	LT	10+06.0	LT					2.4	18.1	
	10+76.0	LT	10+76.0	RT					4.8	22.9	
	10+76.0	LT	10+06.0	LT					15.8	38.7	
	13+28.0	LT	14+15.0	LT					12.0	50.7	
	14+15.0	LT	14+15.0	RT					4.8	55.5	
	14+15.0	LT	15+26.0	LT					14.2	69.7	
	15+26.0	LT	15+25.1	RT					39.9	109.6	
	15+25.1	RT	15+60.4	RT					41.7	151.3	
	15+26.0	LT	16+37.0	LT					117.4	268.7	
	16+37.0	LT	16+37.2	RT					35.2	303.9	
	16+37.2	RT	17+48.0	RT					115.7	419.6	
	17+48.0	RT	18+80	RT					106.4	526.0	
	18+80.0	RT	19+50.3	RT					49.9	575.9	
W Blohm Ave - S Veterans Ave											
	15+60.4	RT	101+10.0	RT					10.3	586.2	
Veterans Ave											
	101+10.0	RT	101+15.0	RT					5.4	591.6	
	101+15.0	RT	101+44.0	RT					3.8	595.4	

Description: EARTH EXCAVATION								Unit: CUBIC YARD			
Location	Begin		End		Quantity Cut (CY)		Quantity Fill (CY)				
	Station	Side	Station	Side	Subtotal	Cumm.	Subtotal	Cumm.			
Blohm Avenue											
	9+52.50		9+75.00		61.7	61.7	0.0	0.0			
	9+75.00		10+00.00		56.6	118.3	0.0	0.0			
	10+00.00		10+52.00		135.3	253.6	1.3	1.3			
	10+52.00		10+76.00		60.3	313.9	2.8	4.1			
	10+76.00		11+00.00		53.3	367.2	4.7	8.8			
	11+00.00		11+50.00		105.0	472.2	16.9	25.6			
	11+50.00		12+00.00		93.5	565.7	26.9	52.5			
	12+00.00		12+50.00		87.3	653.1	31.9	84.3			
	12+50.00		13+00.00		93.8	746.9	24.2	108.5			
	13+00.00		13+16.50		36.1	783.0	3.9	112.4			
	13+16.50		13+30.00		30.3	813.3	2.2	114.6			
	13+30.00		13+50.00		43.9	857.2	3.7	118.3			
	13+50.00		13+90.00		94.5	951.7	7.3	125.6			
	13+90.00		14+00.00		23.0	974.8	2.0	127.6			
	14+00.00		14+48.00		133.2	1108.0	7.8	135.5			
	14+48.00		15+00.00		153.9	1261.9	2.4	137.9			
	15+00.00		15+50.00		151.7	1413.6	0.3	138.1			
	15+50.00		16+00.00		225.2	1638.7	0.0	138.1			
	16+00.00		16+25.00		126.3	1765.0	0.0	138.1			
	16+25.00		16+50.00		110.231	1875.3	0	138.1			
Veterans Dr											
	100+50.00		101+00.00		342.8	2218.1	30.3	168.4			
	101+00.00		101+10.00		54.6	2272.7	5.5	173.9			
	101+10.00		101+40.00		138.8	2411.4	10.9	184.9			
	101+40.00		101+71.50		124.8	2536.2	3.0	187.8			
	101+71.50		102+00.00		91.4	2627.6	1.0	188.8			
	102+00.00		102+10.00		23.8	2651.4	0.7	189.5			
	102+10.00		102+50.00		85.0	2736.4	24.6	214.1			
	102+50.00		103+00.00		83.1	2819.5	63.4	277.5			
	103+00.00		103+50.00		60.1	2879.6	73.8	351.3			
	103+50.00		103+83.00		36.9	2916.4	42.7	394.0			
	103+83.00		104+00.00		18.7	2935.1	17.1	411.1			
	104+00.00		104+17.00		16.2	2951.3	16.9	428.0			
	104+17.00		104+57.00		33.2	2984.5	19.9	447.9			

SCHEDULES OF QUANTITIES