

* 04-00101-00-PV
CONTRACT: 95604

Description: SEEDING, CLASS I								Unit: ACRE	
Location	Begin		End		Quantity (SF)		Quantity (Acre)		
	Station	Side	Station	Side	Subtotal	Cumm.	Subtotal	Cumm.	
Blohm Ave									
	9+54.2	LT	16+48.8	LT	16190.3	16190.3	0.37	0.37	
	9+54.8	RT	10+44.0	RT	1180.0	17370.3	0.03	0.40	
	10+58.0	RT	12+78.2	RT	6610.0	23980.3	0.15	0.55	
	12+84.0	RT	15+80.0	RT	13048.6	37028.9	0.30	0.85	
Woodland Rem.	16+48.8		20+10.0		21925.0	58953.9	0.50	1.35	
Veterans Dr									
	101+86.3	RT	104+57.0	RT	7226.7	66180.6	0.17	1.52	
	100+24.9	LT	103+65.5	LT	5060.2	71240.8	0.12	1.64	
	104+57.0	LT	104+00.5	LT	793.0	72033.8	0.02	1.65	

Description: SODDING								Unit: SQUARE YARD	
Location	Begin		End		Length (FT)	Width (FT)	Area (SF)	Quantity (SY)	
	Station	Side	Station	Side				Subtotal	Cumm.
Blohm Ave									
	9+54.2	LT	12+38.1	LT			757.0	84.1	84.1
	12+61.8	LT	14+35.3	LT			506.0	56.2	140.3
	14+61.05	LT	16+48.8	LT			538.2	59.8	200.1
	9+54.8	RT	10+44.0	RT			135.0	15.0	215.1
	10+58.0	RT	12+78.2	RT			680.0	75.6	290.7
	12+84.0	RT	15+80.0	RT			772.5	85.8	376.5
	16+27.9	RT	16+48.8	RT			63.8	7.1	383.6
Veterans Dr									
	101+86.3	RT	104+17.0	RT			683.9	76.0	76.0
	100+28.8	LT	103+59.5	LT			918.0	102.0	178.0
	104+06.7	LT	104+17.0	LT			23.0	2.6	180.5

564.1

Description: SUB-BASE GRANULAR MATERIAL, TYPE B 4"								Unit: Square Yard	
Location	Begin		End		Length (FT)	Width (FT)	Area (SF)	Quantity (SY)	
	Station	Side	Station	Side				Subtotal	Cumm.
Blohm Ave									
	9+54.2		14+93.0		---	---	18788.4	2087.6	2087.6
	14+93.0		16+48.8		---	---	4718.9	524.3	2611.9
Veterans Dr					---	---			
	100+12.0		104+17.0		---	---	15877.6	1764.2	4376.1

Description: PCC PAVEMENT 8" (JOINTED)								Unit: SQUARE YARD	
Location	Begin		End		Length (FT)	Width (FT)	Area (SF)	Quantity (SY)	
	Station	Side	Station	Side				Subtotal	Cumm.
Blohm Ave									
	9+54.2		14+93.0		---	---	15159.6	1684.4	1684.4
	14+93.0		16+48.8		---	---	4396.3	488.5	2172.9
Veterans Dr					---	---			
	100+12.0		104+17.0		---	---	12804.7	1422.7	3595.6

Description: PCC SIDEWALK 4"								Unit: SQUARE FOOT	
Location	Begin		End		Length (FT)	Width (FT)	Quantity (SF)		
	Station	Side	Station	Side			Subtotal	Cumm.	
Blohm Ave									
	9+54.2	LT	16+48.8	LT			3389.8	3389.8	
W Blohm Ave - S Veterans Dr									
	9+54.8	RT	104+17.0	RT			4514.2	7904.0	
Veteran Dr									
	100+19.2	LT	104+17.0	LT			2029.6	9933.6	

Description: COMBINATION CURB AND GUTTER REMOVAL								Unit: LINEAR FOOT	
Location	Begin		End		Length (FT)	Quantity (LF)			
	Station	Side	Station	Side		Subtotal	Cumm.		
Blohm Ave									
	9+52.5	LT	9+52.5	LT	14.5	14.5	14.5		
	9+21.8	LT	9+01.7	RT	102.0	102.0	116.5		

Description: SIDEWALK REMOVAL								Unit: SQUARE FOOT	
Location	Begin		End		Length (FT)	Width (FT)	Quantity (SF)		
	Station	Side	Station	Side			Subtotal	Cumm.	
Blohm Ave									
	9+17.5	LT	9+17.5	RT	49.3	4	197.0	197.0	

SCHEDULES OF QUANTITIES