

X = SPECIALTY ITEMS				ROADWAY LIGHTING	BRIDGE	TRAFFIC SIGNALS
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN	INTERCHANGE	DDI WEST
				ROADWAY URBAN		
				0004	0021	0010
				90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
54215979	REINFORCED CONCRETE PIPE ELBOW 24"	EACH	4	4		
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	140	140		
550A0660	STORM SEWERS, CLASS A, TYPE 3 15"	FOOT	8	8		
55101200	STORM SEWER REMOVAL 24"	FOOT	137	137		
58600101	GRANULAR BACKFILL FOR STRUCTURES	CU YD	823			823
58700300	CONCRETE SEALER	SQ FT	4,431			4,431
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	162			162
60108206	PIPE UNDERDRAINS, TYPE 2, 6"	FOOT	301	301		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2		
60602800	CONCRETE GUTTER, TYPE B	FOOT	507	507		
66400105	CHAIN LINK FENCE, 4'	FOOT	743	743		
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	2,140	2,140		
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4		
* 66901001	REGULATED SUBSTANCE PRE-CONSTRUCTION PLAN	L SUM	1	1		
* 66901003	REGULATED SUBSTANCE FINAL CONSTRUCTION REPORT	L SUM	1	1		
* 66901006	REGULATED SUBSTANCES MONITORING	CAL DA	35	35		
67100100	MOBILIZATION	L SUM	1	1		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	11,656	11,656		

* SPECIALTY ITEM



USER NAME = jworthington	DESIGNED - TKLUEGEL	REVISED -
PLOT SCALE = 24.0000' / ft.	DRAWN - JWORTHINGTON	REVISED -
PLOT DATE = 8/18/2020	CHECKED - POBRIEN	REVISED -
	DATE - 08/18/2020	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A./P.RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	2020-192-B	WILL	299	9
CONTRACT NO. 62M63				
* FAI 55, FAP 338		ILLINOIS FED. AID PROJECT		

REVISED SHEET 10/21/2020

REV-SEP

MODEL: Default
 FILE: M:\GIS\proj\benesch-pw-bentley.com\benesch-pw-01\Documents\107001\107140_001\Eng_Docs_Ask_Contract\General\162M63-ADV-sht-soq-04.dgn
 D:\62M63 ADV.sht-soq-04.dgn
 63887