

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				ROADWAY	
				BRIDGE		BRIDGE			0005
				SN 081-0106		SN 081-0106			
				0013		0047			
				NHPP FED 90% STATE 10%	IOWA 100%	NHPP FED 90% STATE 10%	IOWA 100%		
URBAN	URBAN	URBAN	URBAN	NHPP FED 90% STATE 10%					
# X5420636	PIPE CULVERTS TO BE CLEANED 36"	FOOT	167					167	
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	61,134	30,567	30,567				
* X7330064	SIGN SUPPORT SPECIAL	EACH	4					4	
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	52,098	200	200			51,698	
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	4,053	25	25			4,003	
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	6,638					6,638	
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	383					383	
X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1	0.5	0.5				
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	140	70	70				
Z0001901	JACK AND REPOSITION BEARINGS	EACH	1	0.5	0.5				
Z0001905	STRUCTURAL STEEL REPAIR	POUND	9,830	4,915	4,915				
Z0004405	HOT-MIX ASPHALT SCARIFICATION	SQ YD	16,354					16,354	
Z0004552	APPROACH SLAB REMOVAL	SQ YD	352	176	176				
Z0005880	BRIDGE HANDRAIL REMOVAL	FOOT	8,382	4,191	4,191				

* SPECIALTY ITEM # NON PARTICIPATING (STATE 100%)

MODEL: Default
 FILE NAME: P:\highway\com.doi.illinois\p01\DOT\Documents\DOT Offices\District 2\Projects\64F78\Program Development\Studies & Plans\Design\CADD\CAD\Sheet\02_64F78_sht-500_Imprnter.dgn

USER NAME = BARTONRW PLOT SCALE = 100.0000' / in. PLOT DATE = Aug-19-2020 12:09:29 PM	DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 280 SECTION (81-18)D&(81-1-1.81-1-2)RS-1 COUNTY ROCK ISLAND TOTAL SHEETS 306 SHEET NO. 16 CONTRACT NO. 64F78 ILLINOIS FED. AID PROJECT
			SCALE: SHEET 11 OF 13 SHEETS STA. TO STA.		

2 REV. 10/28/20
 1 REV. 10/20/20
 REV. 10/7/20
 REV. 9/15/20