

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL
20200100	EARTH EXCAVATION	CU YD	900
25000210	SEEDING, CLASS 2A	ACRE	0.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	23
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	23
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	23
25100115	MULCH METHOD 2	ACRE	0.25
28000400	PERIMETER EROSION BARRIER	FOOT	1765
28000500	INLET AND PIPE PROTECTION	EACH	27
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	12
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	61
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	271
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	9949
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1005
40600990	TEMPORARY RAMP	SQ YD	480
40602985	HOT-MIX ASPHALT BINDER COURSE, IL-9.5, N70	TON	1652
40604052	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "C", N70	TON	1652
40800029	BITUMINOUS MATERIALS (TACK COAT)	POUND	678
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	229
42001300	PROTECTIVE COAT	SQ YD	5624
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	628
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	246
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	7587
42400800	DETECTABLE WARNINGS	SQ FT	136
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	14753
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	555

44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3532
44000600	SIDEWALK REMOVAL	SQ FT	8481
44003100	MEDIAN REMOVAL	SQ FT	234
56109210	WATER VALVES TO BE ADJUSTED	EACH	3
60255500	MANHOLES TO BE ADJUSTED	EACH	10
60260100	INLETS TO BE ADJUSTED	EACH	14
60605000	COMBINATION CONCRETE CURB AND GUTTER, TY B-6.24	FOOT	3761
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	70
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	472
67100100	MOBILIZATION	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	300
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	100
72000100	* SIGN PANEL - TYPE 1	SQ FT	188
72400310	* REMOVE SIGN PANEL - TYPE 1	SQ FT	56
72900100	* METAL POST-TYPE A	FOOT	270
78000100	* THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	224
78000200	* THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8532
78000500	* THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	243
78000600	* THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	796
78000650	* THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	170
78001100	* PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	420
78200020	* CURB REFLECTORS	EACH	13
88000105	* FLASHING BEACON INSTALLATION	EACH	2
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	6
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
Z0036200	* PAINT CURB	FOOT	122

* SPECIALTY ITEMS

HURST-ROSCHIE, INC.
 HILLSBORO, ILLINOIS 62048
 PHONE (217)532-3959



FILE NAME =	USER NAME = jannor	DESIGNED - JJC	REVISED - 10/21/2020
X:\Projects\Current\192-0528 Houseette Lane Reconstruction\Dgn\sum quant.dgn		DRAWN - UJ	REVISED -
Default	PLOT SCALE = 1/8" = 1' in.	CHECKED -	REVISED -
	PLOT DATE = 7/15/2020	DATE - 4-8-2020	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES MOUSETTE LANE				F.A.U. RTE. 9197	SECTION 16-00047-00-RP	COUNTY ST. CLAIR	TOTAL SHEETS 57	SHEET NO. 3
SCALE: NONE	SHEET 1	OF 1	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 97738		

