

PROJECT: GATEWAYS AND CORNER GARDENS AT 87TH STREET
COOK COUNTY / CITY OF CHICAGO

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2005-069 LS	COOK	60	5
STA. 1255+81 (NB I-94) TO STA. 1263+45 (NB I-94)		STA. 1255+15 (SB I-94) TO STA. 1263+40 (SB I-94)		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

60A75

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	100% STATE		100% CITY OF CHICAGO
				DAN RYAN Y003	DAN RYAN Y007	DAN RYAN Y003
▲ 7800600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	12			12
B1400200	HEAVY-DUTY HANDHOLE	EACH	1			1
C2011134	SHRUB, SYRINGA X PERSICA (PERSIAN LILAC) 2' HEIGHT, BALLED AND BURLAPPED	EACH	249	249		
X0326144	TACTILE/DETECTABLE WARNING SURFACE	SQ FT	16			16
B2001770	TREE, CRATAEGUS CRUSGALLI VAR. INERMIS (THORNLESS COCKSPUR HAWTHORN), 3' HEIGHT, BALLED AND BURLAPPED, MULTI-HEADS	EACH	6	6		
A2008748	TREE, ULMUS X FRONTIER (FRONTIER ELM), 3" CALIPER, BALLED AND BURLAPPED, MATCHING HEADS	EACH	9	9		
X5620103	WATER SERVICE LINE 3" (SPECIAL)	FOOT	12			12
Z5001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	0.25	0.25		
K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	3	3		
K0030470	PERENNIAL PLANT, ORNAMENTAL GRASS TYPE	UNIT	21	21		
K1003460	LANDSCAPE MAINTENANCE	CAL MO	11	11		
X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	23	23		
X0320870	BRACED EXCAVATION	CU YD	5			5
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103		
X0322434	LIGHT TOWER, SERVICE PAD, SPECIAL	EACH	2		2	
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	461	461		
X0324525	PLANTING MIX FURNISH AND PLACE 36"	SQ YD	15	15		
X0325102	INSPECTION PIPE 4 INCH	EACH	2			2
X0325103	WATER METER IN VAULT, 2 INCH	EACH	2			2
X0325104	WATER TAP, 2 INCH	EACH	2			2
X0325105	IRRIGATION SYSTEM	SQ YD	610			610
X0325106	IRRIGATION SYSTEMS FALL SHUTDOWN	EACH	2			2
X0325107	IRRIGATION SYSTEMS SPRING STARTUP	EACH	2			2
X0325108	BACKFLOW PREVENTER (RPZ), 2 INCH	EACH	2			2
X0325109	POROUS GRANULAR MATERIAL	CU YD	5	5		
X0325132	SHAPING AND GRADING AT HIGH MAST LIGHT TOWER	SQ YD	45		45	
X0325604	WEED CONTROL, PRE-EMERGENT HERBICIDE	GALLON	1	1		
X0325970	SOIL CONDITIONER, 3"	SQ YD	1195	1195		
X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	67			67
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	310	243		67
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	125.0			125.0
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0027800	GEOTECHNICAL FABRIC	SQ YD	39	39		

▲ - Specialty Items

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 2 OF 2

SCALE: NONE
DATE: JUNE 20, 2008

DRAWN BY: JDF
CHECKED BY: RTM

Rev.