

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY		LANDSCAPING
				URBAN 100% STATE IDOT	ROADWAY CDOT	
25000210	SEEDING, CLASS 2A	ACRE	0.34	0.34		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	79	30		49
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	40	30		30
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	50	30		20
25100630	EROSION CONTROL BLANKET	SQ YD	1634	1634		
28000510	INLET FILTERS	EACH	14	14		
42001300	PROTECTIVE COAT	SQ YD	158		158	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	338		338	
44000300	CURB REMOVAL	FOOT	11		11	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	50		50	
44000600	SIDEWALK REMOVAL	SQ FT	338		338	
44003100	MEDIAN REMOVAL	SQ FT	95		95	
44201357	CLASS C PATCHES, TYPE III, 10 INCH	SQ YD	52		52	
56104600	WATER VALVES 2"	EACH	4		4	
60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	11		11	
60604100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED)	FOOT	20		20	
67100100	MOBILIZATION	LSUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	LSUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12		
<del>67000500</del>	<del>ENGINEER'S FIELD OFFICE, TYPE B</del>	<del>CAL MO</del>	<del>16</del>	<del>16</del>		
K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	17.67			17.67
K0030470	PERENNIAL PLANTS, ORNAMENTAL GRASS TYPE	UNIT	25.30			25.30
X0301407	PERENNIAL PLANTS, GALLON POT	UNIT	34.05			34.05
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52		
X0325103	WATER METER IN VAULT, 2 INCH	EACH	4		4	
X0325104	WATER TAP, 2 INCH	EACH	4		4	
X0325105	IRRIGATION SYSTEM	SQ YD	1250		1250	
X0325106	IRRIGATION SYSTEM FALL SHUT-DOWN	EACH	4		4	
X0325107	IRRIGATION SYSTEM SPRING START-UP	EACH	4		4	
X0325108	BACKFLOW PREVENTER (RPZ), 2 INCH	EACH	4		4	
X0325604	WEED CONTROL, PRE-EMERGENT HERBICIDE	GALLON	1			1

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY		LANDSCAPING
				URBAN 100% STATE IDOT	ROADWAY CDOT	
X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	44		44	
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	95		95	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	LSUM	1	1		
XX005307	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 3" CALIPER, BALLED & BURLAPPED	EACH	15			15
XX006326	TYPE K COPPER PIPE 2"	FOOT	200		200	
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	30		30	
XX152400	SAND CUSHION, 3 INCH	CU YD	3.2		3.2	
Z0013798	CONSTRUCTION LAYOUT	LSUM	1	1		
<del>Z0076600</del>	<del>TRAINEES</del>	<del>HOURL</del>				
<del>C2007010</del>	<del>SHRUB, ROSA RADRAZZ (KNOCK OUT ROSE), CONTAINER GROWN, 3-GALLON</del>	<del>EACH</del>	<del>564</del>			<del>564</del>
B2010020	TREE, AMELANCHIER GRANDIFLORA PRINCESS DIANA (PRINCESS DIANA APPLE SERVICEBERRY), 8' HEIGHT, BALLED AND BURLAPPED	EACH	16			16
X0326146	SOIL CONDITIONER	SQ YD	2659			2659
K1003460	LANDSCAPE MAINTENANCE	CAL MO	12			12

\* DENOTES SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 90/94 (DAN RYAN EXPRESSWAY) 47TH STREET GATEWAY LANDSCAPING AND IRRIGATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: NONE  
DATE: MAY 02, 2008

DRAWN BY: MK  
CHECKED BY: RMG