

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
876	9Y-RS-7	WILL	100	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
CONTRACT NO. 60E52				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
MX033749	PIPE CULVERTREMOVAL, 525MM	METER	12	12				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	60	60				
28000510	INLET FILTERS	EACH	12	12				
50104400	CONCRETE HEADWALL REMOVAL	EACH	6	6				
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	7	7				
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	12				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12				
67100100	MOBILIZATION	L SUM	1	1				
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	305	305				
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	115	115				
M2010110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	206	206				
M2010210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	18	18				
M2020010	EARTH EXCAVATION	CU M	39894	39894				
M2021200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU M	7680	7680				
M2070420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU M	2553	2553				
M2080150	TRENCH BACKFILL	CU M	146	146				
M2113100	TOPSOIL FURNISH AND PLACE, 100MM	SQ M	6000	6000				
M2114100	COMPOST FURNISH AND PLACE, 100MM	SQ M	6000	6000				
M2140100	GRADING AND SHAPING DITCHES	METER	3500	3500				
M2500210	SEEDING, CLASS 2A	HA	0.6	0.6				
M2500310	SEEDING, CLASS 4	HA	0.6	0.6				
M2500400	NITROGEN FERTILIZER NUTRIENT	KG	60	60				
M2500500	PHOSPHORUS FERTILIZER NUTRIENT	KG	37	37				
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	38	38				
M2510630	EROSION CONTROL BLANKET	SQ M	12000	12000				
M2520110	SODDING, SALT TOLERANT	SQ M	2386	2386				

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 1000-2A				
M2800255	TEMPORARY EROSION CONTROL SEEDING	HA	1.2	1.2				
M2800400	PERIMETER EROSION BARRIER	METER	1200	1200				
M2810105	STONE RIPRAP, CLASS A3	SQ M	36	36				
M2820200	FILTER FABRIC	SQ M	36	36				
M3111150	SUB-BASE GRANULAR MATERIAL, TYPE B 150MM	SQ M	1002	1002				
M3550450	HOT-MIX ASPHALT BASE COURSE, 150MM	SQ M	516	516				
M3550500	HOT-MIX ASPHALT BASE COURSE, 200MM	SQ M	486	486				
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	8	8				
M4060300	AGGREGATE (PRIME COAT)	M TON	36	36				
M4060400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	M TON	9	9				
M4060895	CONSTRUCTING TEST STRIP	EACH	2	2				
M4060982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ M	48	48				
M4061005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	M TON	133	133				
M4062135	LEVELING BINDER (MACHINE METHOD), N70	M TON	232	232				
M4063085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	M TON	395	395				
M4063240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	M TON	5885	5885				
M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	121	121				
M4063340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	M TON	963	963				
M4063595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	M TON	866	866				
M4400750	HOT-MIX ASPHALT SURFACE REMOVAL, 50MM	SQ M	3330	3330				
M4400760	HOT-MIX ASPHALT SURFACE REMOVAL, 60MM	SQ M	5084	5084				
M4401165	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 65MM	SQ M	851	851				
M4402000	PAVEMENT REMOVAL	SQ M	3190	3190				
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	320	320				
M4402530	PAVED SHOULDER REMOVAL	SQ M	696	696				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

9/5/2008 9:52:08 AM C:\projects\60E52\60E52.dwg