

**INDEX OF SHEETS**

1. TITLE SHEET
2. INDEX OF SHEETS  
LIST OF APPLICABLE STATE STANDARDS  
GENERAL NOTES
3. SUMMARY OF QUANTITIES
4. COOK COUNTY LOCATION MAP
5. KANE COUNTY LOCATION MAP
6. DUPAGE COUNTY LOCATION MAP
7. WILL COUNTY LOCATION MAP
8. TYPICAL DETAILS FOR STEEL PLATE BEAM  
GUARDRAIL ANCHORAGE REPAIR
9. TYPICAL DETAIL FOR GUARDRAIL ANCHOR BLOCK REPAIR
10. TYPICAL DETAIL TO ANCHOR STEEL PLATE BEAM  
GUARDRAIL ON CONCRETE
11. DETAIL FOR CENTER LONGITUDINAL GUARDRAIL JOINT
12. DETAIL OF STEEL BEAM GUARDRAIL SPECIAL
13. DETAIL OF GUARDRAIL SUPPORT AND END ANCHORAGE
14. DETAIL OF THRIE-BEAM GUARDRAIL WITH MODIFIED OFFSET BLOCK
15. STEEL PLATE BEAM GUARDRAIL STEEL BLOCK-OUT DETAIL
16. CURB REMOVAL (PARTIAL) AND SHOULDER WIDENING  
FOR TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL
17. STEEL BRIDGE RAIL DETAIL
- 18-20. T6 TERMINAL FOR USE WITH 21" HIGH SPBGR
21. TRAFFIC CONTROL DETAIL FOR SHOULDER CLOSURE AND PARTIAL RAMP CLOSURE

**LIST OF STATE STANDARDS**

- |           |   |
|-----------|---|
| 630001-07 | STEEL PLATE BEAM GUARDRAIL  |
| 630301-04 | SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS            |
| 631006-05 | TRAFFIC BARRIER TERMINAL, TYPE 1B                                     |
| 631011-04 | TRAFFIC BARRIER TERMINAL, TYPE 2                                      |
| 631026-04 | TRAFFIC BARRIER TERMINAL, TYPE 5                                      |
| 631031-00 | TRAFFIC BARRIER TERMINAL, TYPE 6                                      |
| 631036-04 | TRAFFIC BARRIER TERMINAL, TYPE 8                                      |
| 635006-02 | REFLECTOR AND TERMINAL MARKER PLACEMENT                               |
| 635011-01 | REFLECTOR MARKER AND MOUNTING DETAILS                                 |
| 701006-02 | OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE              |
| 701011-01 | OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY                            |
| 701101-01 | OFF-RD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE           |
| 701201-02 | LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS ≥ 45 MPH                   |
| 701301-02 | LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS                           |
| 701400-02 | APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY                          |
| 701401-04 | LANE CLOSURE, FREEWAY/EXPRESSWAY                                      |
| 701406-04 | LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY                 |
| 701411-04 | LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEED ≥ 45 MPH |
| 701501-04 | URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED                                 |
| 701606-05 | URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN               |
| 701701-05 | URBAN LANE CLOSURE, MULTILANE INTERSECTION                            |
| 701801-03 | LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE         |
| 701901    | TRAFFIC CONTROL DEVICES   |
| 720011    | METAL POSTS FOR SIGNS, MARKERS & DELINEATORS                          |

**GENERAL NOTES**

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 OR "CUAN" AT (312) 744-700 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED

ALL WORK IS TO BE REPLACED IN KIND OR AS INDICATED ON THE CONTRACT QUANTITY SHEET.

GUARDRAIL WORK WILL INCLUDE ALIGNMENT AS NECESSARY TO RESTORE THE RAIL TO THE ORIGINAL CONDITIONS.

REMOVAL OF DAMAGED MATERIALS WILL INCLUDE DISMANTLING, LOADING, HAULING AND DISPOSAL. THE WORK SITE WILL BE LEFT IN A SAFE AND ORDERLY CONDITION.

NO MATERIAL SHOULD BE LEFT ON OR NEAR THE ROADWAY DURING NON-WORKING HOURS.

ANY NECESSARY TRAFFIC CONTROL WILL BE PROVIDED BY THE CONTRACTOR; APPROPRIATE STANDARDS ARE HEREWITH ATTACHED (SEE COVER SHEET).

THE LIMITS OF THE DAMAGED GUARDRAIL WILL BE MARKED WITH PAINT. THE REPLACEMENT PARTS AND THE QUANTITIES INDICATED ARE WITHIN THESE LIMITS AS MARKED.

REMOVED GUARDRAIL THAT IS NOT REPLACED ON THE SAME DAY MUST BE DELINEATED WITH LIGHTED BARRICADES. NO LOCATIONS WILL BE LEFT WITHOUT EITHER LIGHTED BARRICADES OR RESTORED GUARDRAIL AT ANY TIME.

GUARDRAIL MARKERS SHALL NOT BE ATTACHED TO TERMINAL SECTIONS.

FILE NAME = c:\projects\ml26188\maint.bb.dgn	USER NAME = midyjo	DESIGNED - DRAWN -	REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 49,9999' / IN.	CHECKED -	REVISED -			VAR	2008-058 GRR	VARIOUS	21	2	
	PLOT DATE = 8/28/2008	DATE -	REVISED -			CONTRACT NO. 60F16					
						SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.