



Location	El. a (Beam 2)	El. b (Beam 3)	El. c (Beam 4)	El. d (Beam 5)	El. e (Beam 6)	El. f (Beam 7)	El. g (Beam 8)	El. h (Beam 9)	El. i (Beam 10)
Pier 1	626.42	626.54	626.66	626.77	626.79	626.79	626.75	626.66	626.54
Pier 2	628.44	628.56	628.67	628.76	628.80	628.80	628.76	628.67	628.56
Pier 3	628.75	628.87	628.98	629.07	629.11	629.11	629.07	628.98	628.87

EXIST. BRG. SEAT ELEVATIONS

Note:
Quantities & locations are for information purposes only. It shall be the Contractor's responsibility to verify such dimensions & details in the field and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

BILL OF MATERIAL

Item	Unit	Total
Epoxy Crack Injection	Foot	50.0
Structural Repair of Concrete (Depth equal to or less than 5")	Sq. Ft.	1510.6
Concrete Removal	Cu. Yd.	-----

LEGEND

- Epoxy Crack Injection
- Structural Repair of Concrete (Depth equal to or less than 5")
- Concrete Removal

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PIER REPAIRS
31 ST. STREET OVER M.J. & C.W.I.R.R.
F.A.U. ROUTE 1463 SECTION 159-1010.1B
COOK COUNTY
STATION 217+09.66
STR. NO. 016-0871

SCALE: VERT. _____
HORIZ. _____
DATE: JANUARY 2008

DRAWN BY: JHR
CHECKED BY: CLS