

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1346 & 2626	05-00050-00-CH	COOK/DUPAGE	94	5
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003569				

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y031-1F	Y030-1E
				DEVON AVE & N. ARLINGTON HEIGHTS RD (COOK COUNTY)	S. ARLINGTON HEIGHTS RD (DUPAGE COUNTY)	VILLAGE ITEMS	TRAFFIC SIGNALS	LIGHTING
				70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	276	115	161			
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	742	742				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	771		771			
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	4046	4046				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	37		37			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	352		352			
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1717	1717				
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	11	11				
42001200	PAVEMENT FABRIC	SQ YD	1520	1520				
42001300	PROTECTIVE COAT	SQ YD	12178	10049	2129			
X 42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SQ YD	1108	838	270			
X 42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	18161	15508	2653			
42400800	DETECTABLE WARNINGS	SQ FT	177	50	127			
44000100	PAVEMENT REMOVAL	SQ YD	1350	1160	190			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	805	136	669			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1795	1231	552			
44000300	CURB REMOVAL	FOOT	303	215	88			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6427	4720	1707			
44000600	SIDEWALK REMOVAL	SQ FT	15119	13727	1392			
X 44003100	MEDIAN REMOVAL	SQ FT	22139	17886	4253			
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	170	145	25			
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	975	825	150			
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	155	105	50			
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	170	145	25			
44213200	SAW CUTS	FOOT	2300	1900	400			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	4300		4300			
45200100	JOINT OR CRACK ROUTING (PC CONCRETE PAVEMENT AND SHOULDER)	FOOT	16860	12560	4300			
45200300	JOINT OR CRACK FILLING	POUND	3933	2930	1003			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	72	72				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	231	182	49			
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	549	440	109			

X INDICATES SPECIAL PROVISION  
 ● INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

DATE: 5/27/08  
 DESIGNED BY: KRK  
 CHECKED BY: DJK