

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1346 & 2626	05-00050-00-CH	COOK/DUPAGE	94	9
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003569				

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y031-1F	Y030-1E
				DEVON AVE & N. ARLINGTON HEIGHTS RD (COOK COUNTY) 70% FEDERAL 30% LOCAL	S. ARLINGTON HEIGHTS RD (DUPAGE COUNTY) 70% FEDERAL 30% LOCAL	VILLAGE ITEMS 70% FEDERAL 30% LOCAL	TRAFFIC SIGNALS 70% FEDERAL 30% LOCAL	LIGHTING 70% FEDERAL 30% LOCAL
78300100	PAVEMENT MARKING REMOVAL	SQ FT	447	447				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	24	10	14			
X ● 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1					1
X ● 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L. SUM	1					1
X ● 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	2100				1357	
X ● 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	241				141	100
X ● 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	43				43	
X ● 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	84				46	38
X ● 81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	55				55	
X ● 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	887				517	370
X ● 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	93					93
X ● 81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	362				362	
X ● 81400100	HANDHOLE	EACH	6				6	
X ● 81400200	HEAVY-DUTY HANDHOLE	EACH	4				4	
X ● 81400300	DOUBLE HANDHOLE	EACH	3				3	
● 81603085	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	5506					5506
● 81702460	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 3/0	FOOT	115					115
X ● 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6096				1637	4459
X ● 82500505	LIGHTING CONTROLLER, SPECIAL	EACH	1					1
● 83017200	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 45 FT. M.H., 6 FT. DAVIT ARM	EACH	2					2
● 83017400	LIGHT POLE, ALUMINUM, TRANSFORMER BASE, 45 FT. M.H., 10 FT. DAVIT ARM	EACH	22					22
● 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	230					230
X ● 83600215	LIGHT POLE FOUNDATION, 24" DIAMETER, OFFSET	FOOT	15					15
● 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2					2
● 84200700	LIGHTING FOUNDATION REMOVAL	EACH	2					2
X ● 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1				1	
X ● 85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1				1	
● 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1				1	
X ● 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1676				1676	
X ● 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2353				2353	
X ● 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1452				1452	

X INDICATES SPECIAL PROVISION
● INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

DATE: 5/27/08
DESIGNED BY: KRK
CHECKED BY: DJK