

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1346 & 2626	05-00050-00-CH	COOK/DUPAGE	94	11
SUMMARY OF QUANTITIES				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT M-8003(569)				

CODED PAY ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000-2A			Y031-1F	Y030-1E
				DEVON AVE & N. ARLINGTON HEIGHTS RD (COOK COUNTY)	S. ARLINGTON HEIGHTS RD (DUPAGE COUNTY)	VILLAGE ITEMS	TRAFFIC SIGNALS	LIGHTING
				70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL	70% FEDERAL 30% LOCAL
X ● XX001368	PULL EXISTING CABLE FROM UNIT DUCT	FOOT	345					345
X ● XX006257	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	43		43			
X X0301766	DRILL AND GROUT #6 TIE BARS	EACH	6165	5100	1065			
X X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	9	8	1			
X ● X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	292	183	109			
X ● X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3885				3885	
X X0323381	STORM SEWERS, (WATER MAIN REQUIREMENTS) TYPE 1, 12"	FOOT	116	116				
X X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	190	148	42			
X X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	2907	2907				
X X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	1460	1460				
X X0325405	FILL EXISTING STORM SEWERS	CU YD	1.2		1.2			
X ● X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1				1	
X X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	24	19	5			
X X4023000	TEMPORARY ACCESS (ROAD)	EACH	4	4				
X ● X8050015	SERVICE INSTALLATION, POLE MOUNT	EACH	1				1	
X ● X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1				1	
X ● X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	3897				3897	
X ● X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	837				837	
X ● X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3C, TWISTED, SHIELDED	FOOT	620				620	
X X0007129	DETECTABLE WARNINGS, SPECIAL	SQ FT	83	83				
X X0007130	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 15 1/2"	SQ YD	62		62			
X ● X0325705	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM - LEVEL II	EACH	1				1	
X ● X0007147	REMOVE AND REPLACE LAWN SPRINKLER SYSTEM	FOOT	300			300		
X ● X0007131	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT (SPECIAL)	EACH	24					24
X ● 72000100	SIGN PANEL - TYPE 1	SQ FT	125	101	24			
X ● 72000200	SIGN PANEL - TYPE 2	SQ FT	130	32			98	

X INDICATES SPECIAL PROVISION
 ● INDICATES SPECIALTY ITEM

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES

DATE: 5/27/08
 DESIGNED BY: KRK
 CHECKED BY: DJK