

SCHEDULE OF QUANTITIES

20101000 TEMPORARY FENCE

| FOOT | LOCATION | REMARKS |
|-------------|-----------------|-----------------------------------|
| 295 RT | 342+ 28 TO 344+ | 94 Provide protection of Wetlands |
| 479 RT | 345+ 30 TO 349+ | 95 Provide protection of Wetlands |
| 373 LT | 340+ 95 TO 344+ | 34 Provide protection of Wetlands |
| 615 LT | 344+ 85 TO 350+ | 72 Provide protection of Wetlands |
| 371 LT | 351+ 47 TO 354+ | 85 Provide protection of Wetlands |
| 173 LT | 355+ 8 TO 356+ | 68 Provide protection of Wetlands |
| 2306 | TOTAL | |

20100500 TREE REMOVAL, ACRES

| ACRES | LOCATION | REMARKS |
|-------------|-----------------------|---------|
| 0.55 | LT/RT 339+ 10 TO 359+ | 8 |
| 0.55 | TOTAL | |

25100630 EROSION CONTROL BLANKET

| SQ_YD | LOCATION | REMARKS |
|---------------|--------------------------|---------|
| 817.8 | LT. STA. 341+ 0 TO 344+ | 0 |
| 407.4 | RT. STA. 342+ 0 TO 344+ | 0 |
| 3225.7 | LT. STA. 345+ 50 TO 360+ | 70 |
| 3455.3 | RT. STA. 345+ 50 TO 360+ | 70 |
| 7906.2 | TOTAL | |

28000400 PERIMETER EROSION BARRIER

| FOOT | LOCATION | REMARKS |
|-------------|---------------------------|---------------------------|
| 91 | LT. STA. 339+ 0 TO 1202+ | 43 SW Quad (W. Ebson Rd.) |
| 343 | RT. STA. 339+ 0 TO 1001+ | 77 SE Quad (E. Ebson Rd.) |
| 410 | LT. STA. 1202+ 43 TO 343+ | 97 NW Quad (W. Ebson Rd.) |
| 250 | RT. STA. 1001+ 26 TO 344+ | 32 NE Quad (E. Ebson Rd.) |
| 1556 | LT. STA. 345+ 23 TO 360+ | 71 Along IL 84 |
| 1525 | RT. STA. 345+ 63 TO 360+ | 71 Along IL 84 |
| 4175 | TOTAL | |

28000500 INLET AND PIPE PROTECTION

| EACH | LOCATION | REMARKS |
|----------|-------------------|--------------|
| 1 | RT. STA. 1000+ 75 | E. Ebson Rd. |
| 1 | TOTAL | |

28100107 STONE RIPRAP, CLASS A4

| SQ_YD | LOCATION | REMARKS |
|-------------|-------------------|--------------|
| 27.8 | LT. STA. 1000+ 75 | E. Ebson Rd. |
| 27.8 | TOTAL | |

28200200 FILTER FABRIC

| SQ_YD | LOCATION | REMARKS |
|-------------|-------------------|--------------|
| 27.8 | LT. STA. 1000+ 75 | E. Ebson Rd. |
| 27.8 | TOTAL | |

42001165 BRIDGE APPROACH PAVEMENT

| SQ_YD | LOCATION | REMARKS |
|------------|-----------------|---------|
| 144 | 343+ 95 TO 344+ | 25 |
| 144 | 345+ 29 TO 345+ | 59 |
| 288 | TOTAL | |

42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)

| SQ_YD | LOCATION | REMARKS |
|-----------|-----------------|---------|
| 29 | 343+ 89 TO 343+ | 95 |
| 29 | 345+ 59 TO 345+ | 65 |
| 58 | TOTAL | |

54208665 PIPE CULVERTS, TYPE 2, CORRUGATED STEEL, EQUIVALENT ROUND SIZE 60"

| FOOT | LOCATION | REMARKS |
|-----------|--------------|--------------|
| 84 | 1000+ 75 | E. Ebson Rd. |
| 84 | TOTAL | |

54215805 METAL END SECTIONS, EQUIVALENT ROUND-SIZE 60"

| EACH | LOCATION | REMARKS |
|----------|----------------|--------------|
| 2 | LT/RT 1000+ 75 | E. Ebson Rd. |
| 2 | TOTAL | |

63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A

| FOOT | LOCATION | REMARKS |
|-------------|--------------------------|---------|
| 262.5 | LT. STA. 341+ 8 TO 343+ | 70 |
| 162.5 | RT. STA. 342+ 31 TO 343+ | 93 |
| 1337.5 | LT. STA. 345+ 60 TO 358+ | 98 |
| 1337.5 | RT. STA. 345+ 83 TO 359+ | 21 |
| 3100 | TOTAL | |

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6

| EACH | LOCATION | REMARKS |
|----------|--------------------------|------------------------|
| 1 | LT. STA. 343+ 70 TO 344+ | 14 SW Corner Departing |
| 1 | RT. STA. 343+ 93 TO 344+ | 37 SE Corner Approach |
| 1 | LT. STA. 345+ 16 TO 345+ | 60 NW Corner Approach |
| 1 | RT. STA. 345+ 40 TO 345+ | 83 NE Corner Departing |
| 4 | TOTAL | |

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT

| EACH | LOCATION | REMARKS |
|----------|--------------------------|---------|
| 1 | LT. STA. 340+ 58 TO 341+ | 8 |
| 1 | RT. STA. 341+ 81 TO 342+ | 31 |
| 1 | LT. STA. 358+ 98 TO 359+ | 48 |
| 1 | RT. STA. 359+ 21 TO 359+ | 71 |
| 4 | TOTAL | |

63200310 GUARDRAIL REMOVAL

| FOOT | LOCATION | REMARKS |
|-------------|--------------------------|---------|
| 264 | LT. STA. 341+ 60 TO 344+ | 24 |
| 126 | LT. STA. 343+ 25 TO 344+ | 52 |
| 1501 | RT. STA. 345+ 2 TO 360+ | 3 |
| 1449 | LT. STA. 345+ 31 TO 359+ | 80 |
| 3340 | TOTAL | |

63500105 DELINEATORS

| EACH | LOCATION | REMARKS |
|----------|------------------|---|
| 2 | LT/RT 1000+ 75 | AR Culvert 76" x 48" CMP Elliptical Pipe (60" EQRS) |
| 1 | LT. STA. 340+ 58 | At End of Type 1 (Special) Tangent |
| 1 | RT. STA. 341+ 81 | At End of Type 1 (Special) Tangent |
| 1 | LT. STA. 359+ 48 | At End of Type 1 (Special) Tangent |
| 1 | RT. STA. 359+ 71 | At End of Type 1 (Special) Tangent |
| 6 | TOTAL | |