CONTRACT NO. 66610

FAS RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	34BR	IROQUOIS	49	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

80%/20% FED/STATE

	CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE ACBRS X020-2A	CONSTRUCTION TYPE CODE ACRS 1000	TOTAL
	70106700	TEMPORARY RUMBLE STRIP	EACH		6	6
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT		780	480
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT		4000	4000
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT		500	500
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT		1844	1844
	70400100	TEMPORARY CONCRETE BARRIER	FOOT		540	540
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT		480	480
	70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT		550	550
	70500685	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10	EACH		2	2
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH		4	4
•	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT		4000	4000
•	78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT		500	500
•	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH		24	24
•	78100105	RAISED REFLECTIVE PAVEMENT MARKER(BRIDGE)	EACH		1	1
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH		26	26
*	78200520	BARRIER WALL MARKERS, TYPE B	EACH		2	2
•	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH		8	8
	78300100	PAVEMENT MARKING REMOVAL	SQ FT		340	340
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH		24	24
*	A2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH		5	5
*	A2006920	TREE, QUERCUS PALUSTRIS (PIN OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH		5	5
	X0321156	HIGH VISIBILITY TEMPORARY FENCING	FOOT		1765	1765
	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	272		272 △1
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON		444	444
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON		2322	2322
	X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
	X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1
•	X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH		4	4
	50800515	BAR SPLICERS	EACH	274		274
	Z0021700	EXPANSION JOINT REHABILITATION	FOOT		48	48
	28200200	FILTER FABRIC	SQ YD	500		500
•	Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH		2	2
•	Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH		2	2
*	X7200201	WIDTH RESTRICTION SIGNING	LSUM		1	1

• SPECIALTY ITEM

△1 REVISED 10/22/08

ESCA CONSULTANTS, INC.

DESIGNED BY:	ELH	11/05
DRAWN BY:	CJG	11/05
CHECKED BY:	ELH	04/06
APPROVED BY:	RDP	04/06

SUMMARY OF QUANTITIES
FAS RTE 338 (US 45)
SECTION 34BR
IROQUOIS COUNTY

Aug 18, 2008 - 01:54:01 PM
c:\pw_work\pw1dot\wenzelko\d0635139\Summary PG 4.DGN
EP0500