

HMA SURFACE REMOVAL						
Location	Length	HMA SURF REM		*HMA SURF		
		1 1/2"	HMA SURF	REM	REM VAR DEPTH	
	FT	SO YD	(DECK)	SO YD		
EASTBOUND LANES	-0+90	54+47.84	5537.84			
	Gap (SN 006-0001)	54+47.84	56+06.01	158.17		
		56+06.01	64+85.	878.99	2344.0	
	CH 10 (SN 006-0122)	64+85.	67+15.	280.00		1182.2
		67+15.	79+41.91	1226.91	3271.8	
	Gap (SN 006-0003)	79+41.91	80+75.41	133.50		
		80+75.41	158+15.	7739.59	20638.9	
	TR 40 (SN 006-0122)	158+15.	160+45.	280.00		1182.2
		160+45.	182+00.97	2155.97	5749.3	
	Gap (SN 006-0005)	182+00.97	183+76.92	175.95		
		183+76.92	202+00.35	1823.43	4862.5	
	Gap (SN 006-0007)	202+00.35	203+98.6	198.25		
		203+98.6	251+31.	4732.40	12619.7	
	CH 29 (SN 006-0121)	251+31.	253+61.	280.00		1182.2
		253+61.	422+30.5	16869.50	44985.3	
	GAP (SN 006-0009)	422+30.5	423+99.5	169.00		
		423+99.5	426+45.5	246.00		1038.7
	(SN 006-0011)	426+45.5	427+95.67	150.17		
		427+95.67	455+05.	2709.33	7224.9	
	Exit Terminal (D)	455+05.	461+67	662.00	1765.3	
	461+67.	472+53	1086.00	2896.0		
Ent. Terminal <sup>1/4</sup>	472+53.	477+30	477.00	1272.0		
RR (SN 006-0013)	477+30.	479+60	280.00		1550.0	
	479+60.	483+63	403.00	1074.7		
	483+63.	504+01	2038.00	5434.7		
WESTBOUND LANES	-0+90	54+54.	5537.84	14767.6		
	Gap (SN 006-0002)	54+54.	56+12.16	158.16		
		56+12.16	64+85.	872.84	2327.6	
	CH 10 (SN 006-0122)	64+85.	67+15.	280.00		1182.2
		67+15.	79+19.59	1204.59	3212.2	
	Gap (SN 006-0004)	79+19.59	80+63.09	143.50		
		80+63.09	158+15.	7751.91	20671.8	
	TR 40 (SN 006-0122)	158+15.	160+45.	280.00		1182.2
		160+45.	181+27.08	2082.08	5552.2	
	Gap (SN 006-0006)	181+27.08	183+03.08	176.00		
		183+03.08	201+61.4	1858.32	4955.5	
	Gap (SN 006-0008)	201+61.4	203+59.65	198.25		
		203+59.65	251+31.	4771.35	12723.6	
	CH 29 (SN 006-0121)	251+31.	253+61.	280.00		1182.2
		253+61.	341+05.	8744.00	23317.3	
	CH 15 (SN 006-0117)	341+05.	343+35.	280.00		1182.2
		343+35.	422+60.5	7925.50	21134.7	
	Gap (SN 006-0010)	422+60.5	423+69.5	109.00		
		423+69.5	425+44.91	175.41		740.6
	(SN 006-0012)	425+44.91	426+93.66	148.75		
	426+93.66	450+57.95	2364.29	6304.8		
Ent. Terminal (A)	450+57.95	462+08	1150.05	3066.8		
	462+08	471+73	965.00	2573.3		
Exit Terminal (B)	471+73	478+36	663.00	1768.0		
	478+36	504+01	2565.00	6840.0		
Ramps	Ent. Terminal (A)	450+57.95	462+08	1150.05	1597.3	
	Ramp A	0+77	16+19.4	1542.40	2742.0	
	Exit Terminal (B)	471+73	478+36	663.00	1362.8	
	Ramp B	0+00	15+15	1515.00	2693.3	
	Ent. Terminal <sup>1/4</sup>	472+53	483+63	1110.00	2281.7	
	Ramp C	0+77	12+16.93	1139.93	2026.5	
	Exit Terminal (D)	455+05	461+67	662.00	1360.8	
	Ramp D	0+00	14+40	1440.00	2560.0	
Totals				274746.4	1262.0	11604.8

\*SEE DETAIL FOR ADDITIONAL INFORMATION

MAINTENANCE CROSSOVER WIDENING AND OVERLAY		
STATION	AGG BSE CSE TYPE A, 8"	HMA SURF CSE CLASS E
	SO YD	TON
1+50	94	37
14+00	94	37
296+50	94	37
432+00	94	37
494+00	94	37
TOTALS	470	185

HMA SURFACE REMOVAL 2"					
LOCATION	STATION TO STATION	LENGTH	HMA SURF REM 2"	HMA SC "D" N70	
			SO YD	TON	
EASTBOUND	HENRY CO LINE	0+00 TO 54+47.84	5447.8	1210.6	135.6
	(SN 006-0001)	GAP			
	(SN 006-0003)	56+06.01 TO 79+41.91	2335.9	519.1	58.1
	(SN 006-0005)	80+75.41 TO 182+00.97	10125.6	2250.1	252.0
	(SN 006-0007)	183+76.92 TO 202+00.35	1823.4	405.2	45.4
	(SN 006-0009)	203+98.6 TO 422+30.5	21831.9	4851.5	543.4
	(SN 006-0011)	423+99.5 TO 426+45.5	246.0	54.7	6.1
	(SN 006-0011)	GAP			
	(SN 006-0011)	427+95.67 TO 503+11	7515.3	1670.1	187.0
	WESTBOUND	HENRY CO LINE	0+00 TO 54+54.00	5454.0	1212.0
(SN 006-0002)		GAP			
(SN 006-0004)		56+12.16 TO 79+19.59	2307.4	512.8	57.4
(SN 006-0006)		80+63.09 TO 181+27.08	10064.0	2236.4	250.5
(SN 006-0006)		GAP			
(SN 006-0008)		183+03.08 TO 201+61.4	19978.3	4439.6	497.2
(SN 006-0008)		GAP			
(SN 006-0010)		203+59.65 TO 422+60.05	21900.4	4866.8	545.1
(SN 006-0010)		GAP			
(SN 006-0012)		423+69.5 TO 425+44.91	175.4	39.0	4.4
(SN 006-0012)	GAP				
		426+93.66 TO 503+11	7617.3	1692.7	189.6
GRAND TOTAL				25960.6	2907.6

FILE NAME =	USER NAME = braboygc	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwork\p\dot\braboygc\dms32763\dets11s.dgn		DRAWN - ---	REVISED - ---		SCALE: -----	SHEET NO. --- OF --- SHEETS	STA. ----- TO STA. -----	80	06-1,2RS-3, I	BUREAU	116	10
		CHECKED - ---	REVISED - ---					CONTRACT NO. 66623				
		DATE - -----	REVISED - ---					FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				