

STAGE CONSTRUCTION ITEMS										
LOCATION	STR NO.	LEN	TEMP CONC BARR EACH	RELOC TEMP CONC BAR EACH	IMPACT ATT. TEMP NON-REDIRECT. TL3 EACH	IMPACT ATT RELOCATE NON-REDIRECT. NR, TL3 EACH	WORK ZONE PVT MK REMOVAL(1) SQ FT	PAVEMENT MARKING REMOVAL(2) FOOT	WET TEMP PVT TAPE, TYPE III-4"	
									WHITE FOOT	YELLOW FOOT
STAGE I										
199+87 TO 204+40	006-0007	453	453.0		1					
201+00 TO 205+80	006-0008	480	480.0		1					
419+98 TO 424+62	006-0009	464	464.0		1					
422+00 TO 429+85	006-0010	785	785.0		1					
STAGE II										
200+86 TO 206+18	006-0008	532	52.0	480		1				
199+76 TO 204+50	006-0007	474	21.0	453		1				
420+38 TO 424+70	006-0009	432		432		1				
421+90 TO 429+10	006-0010	720		720		1				
EBL										
STAGE I										
186+50 TO 204+40	006-0007	1790					597			1790.0
196+50 TO 208+00	006-0007	1150					383	1150.0	1150.0	
400+73 TO 429+00	006-0009	2827					942			2827.0
419+00 TO 432+00	006-0009	1300					433	1300.0	1300.0	
STAGE II										
186+40 TO 204+50	006-0007	1810					603			1810.0
199+40 TO 206+50	006-0007	710						710.0		710.0
400+50 TO 429+00	006-0009	2850					950		2850.0	
418+90 TO 432+00	006-0009	1310					437	1310.0		1310.0
WBL										
STAGE I										
198+86 TO 209+10	006-0008	1024					341	1024.0	1024.0	
201+00 TO 219+10	006-0008	1810					603			1810.0
419+00 TO 430+15	006-0010	1115					372	1115.0	1115.0	
422+00 TO 445+00	006-0010	2300					767			2300.0
STAGE II										
198+86 TO 206+25	006-0008	739					245	735.0		735.0
200+86 TO 219+26	006-0008	1840					613		1840.0	
421+90 TO 445+00	006-0010	2310					770	2310.0	2310.0	
418+90 TO 424+05	006-0010	515					880			2640.0
TOTALS			2255.0	2085.0	4.0	4.0	8936.9	9654.0	13399.0	14122.0

(1) FOR THE REMOVAL OF THE WET WEATHER TAPE
(2) FOR THE REMOVAL OF EXISTING PAVEMENT MARKINGS