



#1 EMBANKMENT SLOPE ABOVE HEADWALL IS FLATTER THAN 2:1, PROVIDE WINGS FOR 2:1 SLOPE

BILL OF MATERIALS (FOR INFO ONLY-PAY FOR AS EACH)				
REBAR #4 v BARS		REBAR WEIGHT	CONCRETE REMOVAL	CONCRETE HEADWALL REPAIR
#	LENGTH	POUNDS	CU YD	CU YD
4	27"	6	0.2	0.2

NOTE-ALL WORK ON THIS PAGE, INCLUDING THE REMOVAL OF A PORTION OF THE EXISTING WINGWALL, SHALL BE PAID FOR AS CONCRETE HEADWALL REPAIR-SEE SPECIAL PROVISIONS

STA 381+00 (LT)

