

# SUMMARY OF QUANTITIES

CONTRACT NO. 66667				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	129 BR	KENDALL	61	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL 80% FED 20% STATE	ROADWAY 1000	BRIDGE	BRIDGE
					EXIST. SN 047-0016 PROP. SN 047-2019 X078-2A	EXIST. SN 047-0046 PROP. SN 047-2020 X988-2A
70100460	TRAFFIC CONTROL AND PROTECTION STANDARD 701306	Σ SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	Σ SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	45		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3034	3034		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1058	1058		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	474	474		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	474	474		
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	1310	1310		
* 78001130	PAINT PAVEMENT MARKING-LINE 6"	FOOT	216	216		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	25	25		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	460	460		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9		
XX000061	STUMP REMOVAL	EACH	2	2		
△ X0321100	GEOTEXTILE RETAINING WALL	△ SQ FT	76		76	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	470		470	
X0325751	DRIVING SOLDIER PILES	FOOT	302		302	
* X7200201	WIDTH RESTRICTION SIGNING	Σ SUM	1	1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		

\* SPECIALTY ITEM  
 △ REVISED 10/28/08

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE: VERT. NOT TO SCALE  
 HORIZ. NOT TO SCALE  
 DATE 09/10/2007

DRAWN BY C. SUNTKEN  
 CHECKED BY M. ZELINSKAS

PLOT DATE = Aug 06, 2008 - 02:31:17 PM  
 PLOT SCALE = 50.000000 / 1 IN  
 USER NAME = wenzelko