


NOTES:
 1. TEMPORARY RAMP QUANTITIES SHOWN ON THIS SHEET REFLECT QUANTITIES REQUIRED FOR TRAFFIC DURING STAGE 2 CONSTRUCTION. AN ADDITIONAL TOTAL OF 18 SQ YD - TEMPORARY RAMP WILL BE NECESSARY ONCE STAGE 2 CONSTRUCTION IS COMPLETED.

LEGEND

- TRAFFIC SIGNALS
- TRAFFIC SIGNALS WITH MICROWAVE DETECTORS
- DRUM WITH STEADY BURNING LIGHT
- STOP LINE 24"
- IMPACT ATTENUATORS, TEMPORARY (FULLY-REDIRECTIVE, NARROW) TEST LEVEL 3
- DOUBLE VERTICAL PANEL
- TYPE C BI-DIRECTIONAL REFLECTOR
- TYPE III BARRICADE WITH FLASHING LIGHTS
- STEADY BURNING LIGHTS AND DOUBLE VERTICAL PANELS
- WORK AREA
- SIGN
- HMA BASE COURSE WIDENING, 8"
- TEMPORARY HMA BASE COURSE WIDENING 8"
- DIRECTION OF TRAFFIC



FILE NAME = sheets02.dgn	USER NAME = #USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STAGE 2 CONSTRUCTION & TRAFFIC CONTROL			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 20,0000' / IN.	DRAWN -	REVISED -					326	119 BR	GRUNDY	68	15
	PLOT DATE = 8/13/2008	CHECKED -	REVISED -					CONTRACT NO. 66687				
		DATE -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
				SCALE: 1"=20'			SHEET NO. OF SHEETS STA. 580+00 TO STA. 585+00					