CONTRACT NO. 66731

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	*	**	219	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

* (06-14 & 50-8)RS-1(14B,B-1,VB,VB-1,VB-2,VB-3)BR

** BUREAU & LASALLE

CODE NO	ITEM	UNIT	TOTAL QTY	90% FED. 10% STATE ACIM ROADWAY BUREAU COUNTY I000	LASALLE COUNTY I000	90% FED. 10% STATE ACIM EXIST. SN 006-0032(EB) PROP. SN 006-0165 X071-2A	80% FED. 20% STATE ACBRI EXIST. SN 006-0033(WB) PROP. SN 006-0166 X071-2A	90% FED. 10% STATE ACIM CONSTRUCTION TYPE CODE 006-0034 (TBR) C000	006-0035 (TBR) C000	EXIST. SN 006-0036(EB) PROP. SN 006-0167 X171-2A	EXIST. SN 006-0037(WB) PROP. SN 006-0168 X171-2A
44201055	CLASS B PATCHES, TYPE II, 17 INCH	SQ YD	2773	2413	360						
44201057	CLASS B PATCHES, TYPE III, 17 INCH	SQ YD	496	464	32						
44201053	CLASS B PATCHES, TYPE IV, 17 INCH	SQ YD	407	407	0						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3176	2093	1083						
48203045	HOT-MIX ASPHALT SHOULDERS, 12"	SQ YD	626	626							
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		1						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	6			1	1	1	1	1	1
50157300	PROTECTIVE SHIELD	SQ YD	476							238	238
50200100	STRUCTURE EXCAVATION	CU YD	1700			187	187			663	663
50300225	CONCRETE STRUCTURES	CU YD	800.6			120.2	120.2			280.1	280.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	989.2			262	262			232.6	232.6
50300260	BRIDGE DECK GROOVING	SQ YD	2742			718	718			653	653
50300280	CONCRETE ENCASEMENT	CU YD	29.6			8.6	8.6			6.2	6.2
50300300	PROTECTIVE COAT	SQ YD	3430			898	898			817	817
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			0.25	0.25			0.25	0.25
50500505	STUD SHEAR CONNECTORS	EACH	14400			3096	3096			4104	4104
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	359,690			75640	75640			104205	104205
50800515	BAR SPLICERS	EACH	320			80	80			80	80
51100100	SLOPE WALL 4 INCH	SQ YD	138							69	69
51100500	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	1324							662	662
51201400	FURNISHING STEEL PILES HP10X42	FOOT	1584							792	792
51201500	FURNISHING STEEL PILES HP10X57	FOOT	682			341	341				
51201600	FURNISHING STEEL PILES HP12X53	FOOT	3680							1,840	1,840
51201610	FURNISHING STEEL PILES HP12X63	FOOT	682			341	341				
51202000	FURNISHING STEEL PILES HP14X102	FOOT	1024			512	512				
51202305	DRIVING PILES	FOOT	7,652			1194	1194			2,632	2,632
51203400	TEST PILE STEEL HP10X42	EACH	4							2	2
51203500	TEST PILE STEEL HP10X57	EACH	1			1					
51203600	TEST PILE STEEL HP12X53	EACH	4							2	2
51203610	TEST PILE STEEL HP12X63	EACH	1				1				
51205200	TEMPORARY SHEET PILING	SQ FT	796							398	398
51500100	NAME PLATES	EACH	4			1	1			1	1
54215547	METAL END SECTIONS 12"	EACH	8	8							
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	2	2							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	140	140							
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	24	24							
~~54215547~~	~~METAL END SECTIONS 12"~~	~~EACH~~	~~8~~	~~8~~							
54215559	METAL END SECTIONS 24"	EACH	2	2							
55100700	STORM SEWER REMOVAL 15"	FOOT	120	120							
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	310			87	87			68	68
60100945	PIPE DRAINS 12"	FOOT	640	640							

* SPECIALTY ITEMS

PLOT DATE = Sep 19, 2008 - 8:46:12 AM
FILE NAME = c:\pw_work\IDOT\GRABOTF\C\dms32861\details.dgn
PLOT SCALE = 1000.0000 ' / IN.
USER NAME = brabogpo

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES