

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	*	**	219	21

STA. _____ TO STA. _____
 FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT
 *106-14 & 50-8)RS-1(14B,B-1,VB,VB-1,VB-2,VB-3)BR

** BUREAU & LASALLE

PAVEMENT MARKINGS

LOCATION	LENGTH	THPL	THPL	THPL	THPL	THPL	THPL	POLY UREA	POLY UREA	POLY UREA	TEMP	TEMP	TEMP	TEMP	TEMP	TEMP	RAISED	RAISED	BR	SHORT	WORK	DELIN	DELIN	
		PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	PVT	REF	REF	RAISED	TERM	ZONE	REM	DELIN	
		MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MK LN	MKR	MKR	REF	PVT	PVT	MKR	DELIN	
		4"	4"	6"	8"	12"	24"	4"	4"	6"	4"	4"	6"	8"	12"	24"	PVT	PVT	MKR	PVT	PVT	MKR	DELIN	
		WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE	WHITE	YELLOW	WHITE	WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE	REM		MKR		REM			
	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	EACH	EACH	EACH	FT	SO FT	EACH	EACH	
BUREAU CO (EB)																								
STA 1803+19 TO STA 1815+21.84 (BK)	RT	1203																						
STA 275+00 (AH) TO 298+64.83	RT	2365	2365																					
GAP SW OFF RAMP TO IL 89	RT																							
GORE STA 301+10.14 TO STA 303+44.09	RT	234				234									234									
STA 303+44 TO STA 321+73.56	RT	1830	1829																					
GORE STA 321+73.56 TO STA 323+78.27	RT	205				205																		
GAP SE ON RAMP FROM IL 89	RT																							
STA 330+42 TO STA 395+00 (BK)	RT	6458	6458																					
STA 395+06.49 (AH) TO STA 399+07.07	RT	401	199																					
CONC BR APPR STA 399+07.07 TO STA STA 399+37.07	RT	30						30	30	8	30													
SN 006-0165 STA 399+37.07 TO STA 401+07.07	RT	170						170	170	39	170						3	3	3					
CONC BR APPR STA 401+07.07 TO STA 401+37.07	RT	30						30	30	8	30													
STA 401+37.07 TO STA 412+53.48	RT	1116	1116																			134	45	
CONC BR APPR STA 412+53.48 TO STA 412+83.48	RT	30						30	30	8	30													
SN 006-0167 STA 412+83.48 TO STA 414+38.59	RT	155						155	170	39	155							3	3	3				
CONC BR APPR STA 414+38.59 TO STA 414+68.59	RT	30						30	30	8	30													
STA 414+68.59 TO STA 462+39.33	RT	4771	4771																			572	191	
STA 1803+19 TO STA 1815+21.84 (BK)	CL	1203				301									301			30	30			1925	642	
STA 275+00.00 (AH) TO STA 300+00.00 (BK)	CL	2500				625									625			63	63			4000	1333	
STA 299+98.81 (AH) TO STA 395+00.00 (BK)	CL	9501				2375									2375			238	238			15202	5067	
STA 395+06.49 (AH) TO STA 462+39.33	CL	6733				1683									1683			168	168			10773	3591	
STA 1803+19 TO STA 1815+21.84 (BK)	LT	1203				1203									1203									
STA 275+00.00 (AH) TO STA 300+00.00 (BK)	LT	2500				2500									2500									
STA 299+98.81 (AH) TO STA 395+00.00 (BK)	LT	9501				9501									9501									
STA 395+06.49 (AH) TO STA 462+39.33	LT	6733				6733									6733									
BUREAU CO (WB)																								
STA 1803+19 TO STA 1815+21.84 (BK)	RT	1203	1203																					
STA 275+00.00 (AH) TO STA 300+00.00 (BK)	RT	2500																						
STA 299+98.81 (AH) TO STA 395+00.00 (BK)	RT	9501				9501																		
STA 395+06.40(AH) TO STA 462+39.33	RT	6733				6733																		
STA 1803+19 TO STA 1815+21.84 (BK)	CL	1203				301									301			30	30			1925	642	
STA 275+00.00 (AH) TO STA 300+00.00 (BK)	CL	2500				625									625			63	63			4000	1333	
STA 299+98.81 (AH) TO STA 395+00.00 (BK)	CL	9501				2375									2375			238	238			15202	5067	
STA 395+06.40(AH) TO STA 462+39.33	CL	6733				1683									1683			168	168			10773	3591	
STA 1803+19 TO STA 1815+21.84 (BK)	LT	1203	1203																			144	48	
STA 275+00.00 (AH) TO STA 293+61.32	LT	1861	1861																			223	74	
GAP NW ON RAMP TO IL 89	LT																							
GORE STA 300+94.72 TO STA 302+11.72	LT	117				117																		
STA 302+11.72 TO STA 321+01.79	LT	1890	1890																					
GORE STA 321+01.79 TO STA 323+16.38	LT	215				215																		
GAP NE OFF RAMP TO IL 89	LT																							
STA 326+57.93 TO STA 395+00.00 (BK)	LT	6842	6842																					
STA 395+06.40 (AH) TO STA 399+07.07	LT	401	401																			821	274	
CONC BR APPR STA 399+07.07 TO STA STA 399+37.07	RT	30						30	30	8	30											48	16	
SN 006-0165 STA 399+37.07 TO STA 401+07.07	RT	170						170	170	43	170							3	3	3				
CONC BR APPR STA 401+07.07 TO STA 401+37.07	RT	30						30	30	8	30													
STA 401+37.07 TO STA 412+53.48	RT	1116	1074																			129	43	
CONC BR APPR STA 412+53.48 TO STA 412+83.48	RT	30						30	30	8	30													
SN 006-0167 STA 412+83.48 TO STA 414+38.59	RT	155						155	155	39	155													
CONC BR APPR STA 414+38.59 TO STA 414+68.59	RT	30						30	30	8	30													
STA 414+68.59 TO STA 462+39.33	RT	4814	4814																			578	193	
BUREAU CO (EB & WB) TOTAL																								
			36026	39874	9968	771	0	0	890	905	224	36916	39874	9968	771	0	0	1010	1010	12	68099	22700	104	104
LASALLE CO (EB)																								
STA 462+39.33 TO STA 480+97.57	RT	1858	1858																					
GAP SW OFF RAMP TO PLANK RD	RT																							
GORE STA 485+14.23 TO STA 490+07.14	RT	493				493																		
STA 490+07.14 TO STA 504+17.38	RT	1410	1410																					
GORE STA 504+17.38 TO STA 506+97.31	RT	280				280																		
GAP SE ON RAMP FROM PLANK RD	RT																							
STA 521+92.38 TO STA 533+50	RT	1158	1158																					
STA 462+39.33 TO STA 533+50	CL	7111				1778												178	178			11377	3792	
STA 462+39.33 TO STA 533+50	LT	7111				7111																		
LASALLE CO (WB)																								
STA 462+39.33 TO STA 533+50	RT	7111				7111																		
STA 462+39.33 TO STA 533+50	CL	7111				1778																		
STA 462+39.33 TO STA 470+69.52	LT	830	830																					
GAP NW RAMP ON RAMP FROM PLANK ROAD	LT																							
GORE STA 485+03.87 TO STA 488+29.94	LT	326				326																		
STA 488+29.94 TO STA 502+53.82	LT	1424	1424																					
GORE STA 502+53.82 TO STA 507+30.58	LT	477				477																		
GAP NE OFF RAMP TO PLANK RD	LT																							
STA 511+45.84 TO STA 533+50	LT	2204	2204																					
LASALLE CO TOTAL																								
			8884	14222	3556	1576	0	0	0	0	0	8884	0	0	1576	0	0	356	356	0	23820	7939	40	40
GRAND TOTAL																								
			44910	54096	13524	2346	0	0	890	905	224	45800	39874	9968	2346	0	0	1366	1366	12	91920	30639	144	144

- STA EQUATION
- (1) STA 1815+21.84 BK = STA 275+00 AH
- (2) STA 300+00.00 BK = STA 299+98.81 AH
- (3) STA 395+00 BK = TO STA 395+06.40 AH

PLOT DATE = Aug 29, 2008 - 12:23:12 PM
 PLOT SCALE = 1/8" = 100'-0"
 USER NAME = brab