

**SUMMARY OF QUANTITIES**

CODE #	ITEM	UNIT	QUANTITY	HBP FUNDING 80% FEDERAL 20% STATE ROADWAY 1000	HBP FUNDING 80% FEDERAL 20% STATE SN 029-0066 X081-2A
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	102	0	102
60100945	PIPE DRAINS 12"	FOOT	74	74	0
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	170	0	170
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	2	2	0
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	0
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	275	275	0
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	0
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	0
63200310	GUARDRAIL REMOVAL	FOOT	400	400	0
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	2	2	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	0
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	3	3	0
67100100	MOBILIZATION	L SUM	1	1	0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	0
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	160	160	0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4818	4818	0
70300280	TEMPORARY PAVEMENT MARKING- LINE 24"	FOOT	22	22	0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1965	1965	0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	500	500	0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	425	425	0
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	2600	2600	0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9	0
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2	0

**SUMMARY OF QUANTITIES**

CODE #	ITEM	UNIT	QUANTITY	HBP FUNDING 80% FEDERAL 20% STATE ROADWAY 1000	HBP FUNDING 80% FEDERAL 20% STATE SN 029-0066 X081-2A
78200405	GUARDRAIL MARKERS	EACH	11	11	0
78200500	BARRIER WALL MARKERS	EACH	21	21	0
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	705	705	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11	11	0
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	124	124	0
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	860	0	860
▲ X2503100	MOWING	UNIT	5	5	
XB620020	UNINTERRUPTABLE POWER SUPPLY	EACH	1	1	0
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	0
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2	0
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	0
+ Z0076600	TRAINEES	HOUR	500	500	

+ FUNDING CODE Y080

▲ NP 100% STATE

**HAMPTON, LENZINI & RENWICK, INC.**  
CIVIL & STRUCTURAL ENGINEERS  
LAND SURVEYORS

3085 STEVENSON DRIVE, SUITE 201  
SPRINGFIELD, ILLINOIS 62703  
(217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-37-0003-1    DATE: 08/13/08  
DESIGNED: L.F.S.    CHECKED: S.W.M.    DRAWN: D.T.M.

**SUMMARY OF QUANTITIES**  
F.A.P. ROUTE 665 (IL 116) OVER LITTLERS CREEK  
SECTION (144-B) BR  
FULTON COUNTY