

# SUMMARY OF QUANTITIES

F. A. S. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-24-BS-5	EUILTON	282	6
STA.	TO STA.			
FED. ROAD DIST. NO. 5	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			URBAN				CONSTRUCTION TYPE CODE														
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A 100% FED	TUNNEL SIDE WALK REM SFTY-1B 100% CITY	TRAFFIC SIGNALS Y031-1F 100% STATE	SIDEWALK SFTY-1B 50% STATE 50% CITY														
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	187.4	187.4																	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	525.1	525.1																	
20100500	TREE REMOVAL, ACRES	ACRE	0.6	0.6																	
20200100	EARTH EXCAVATION	CU YD	17399	16187	1212																
20200500	EARTH EXCAVATION (WIDENING)	CU YD	5185	5185																	
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	978	978																	
20400800	FURNISHED EXCAVATION	CU YD	3106	2934	172																
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	48.3	4.3	44																
20800150	TRENCH BACKFILL	CU YD	1952.3	1181.3	771																
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	612.7	462	150.7																
21101615	TOP SOIL FURNISH AND PLACE, 4"	SQ YD	44145	44145																	
* 25000110	SEEDING, CLASS 1A	ACRE	9.2	9.2																	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1038	1038																	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1038	1038																	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1038	1038																	
* 25100115	MULCH, METHOD 2	ACRE	9.2	9.2																	
* 25100630	EROSION CONTROL BLANKET	SQ YD	38	38																	
* 25200110	SODDING, SALT TOLERANT	SQ YD	16975	16975																	
* 25200200	SUPPLEMENTAL WATERING	UNIT	356	356																	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	920	920																	
28000300	TEMPORARY DITCH CHECKS	EACH	180	180																	
28000400	PERIMETER EROSION BARRIER	FOOT	4790	4790																	
28000500	INLET AND PIPE PROTECTION	EACH	310	310																	
28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	1567	1567																	
28200200	FILTER FABRIC	SQ YD	1605.5	1567	38.5																
31100200	SUB-BASE GRANULAR MATERIAL, TYPE A	CU YD	943	943																	
35501308	HOT - MIX ASPHALT BASE COURSE, 6"	SQ YD	657	657																	
35501316	HOT - MIX ASPHALT BASE COURSE, 8"	SQ YD	1755	1755																	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	301.7	301.7																	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1030	1030																	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	31.6	31.6																	
40600300	AGGREGATE (PRIME COAT)	TON	185.3	185.3																	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2																	

\* SPECIALTY ITEM

REVISD 10/22/08