

SUMMARY OF QUANTITIES

F. A. E. DIST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-24 BS-5	EUILTON	282	7
STA.	TO STA.			
FED. ROAD DIST. NO. 3	BLM#	FED. AID PROJECT		

SUMMARY OF QUANTITIES			URBAN				CONSTRUCTION TYPE CODE														
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A 100% FED	TUNNEL SIDE WALK REM SFTY-18 100% CITY	TRAFFIC SIGNALS Y031-1F 100% STATE	SIDEWALK SFTY-18 50% STATE 50% CITY														
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	953	953																	
40600990	TEMPORARY RAMP	SQ YD	229.7	229.7																	
40603080	HOT - MIX ASPHALT BINDER COURSE, IL - 19 .0, N50	TON	19338.3	19338.3																	
40603360	HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	4875.4	4875.4																	
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	513.2	513.2																	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1284	1284																	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	544	544																	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	34868.5				34868.5														
44000100	PAVEMENT REMOVAL	SQ YD	8072	8072																	
44000151	HOT - MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	48546	48546																	
44000157	HOT - MIX ASPHALT SURFACE REMOVAL, 2 "	SQ YD	1673	1673																	
44000198	HOT - MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1011	1011																	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	6973	6973																	
44000300	CURB REMOVAL	FOOT	48	48																	
44000400	GUTTER REMOVAL	FOOT	1304	1304																	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2337	2337																	
44000600	SIDEWALK REMOVAL	SQ FT	35040	8940	26100																
44004000	PAVED DITCH REMOVAL	FOOT	125	125																	
44004250	PAVED SHOULDER REMOVAL	SQ YD	4441	4441																	
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	185.5	185.5																	
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	233.8	233.8																	
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	111		111																
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	20510	20510																	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1678	1678																	
48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SQ YD	8836	8836																	
48203049	HOT - MIX ASPHALT SHOULDERS, 13"	SQ YD	285.6	285.6																	
50104400	CONCRETE HEADWALL REMOVAL	EACH	21	21																	
50105220	PIPE CULVERT REMOVAL	FOOT	3259.7	3259.7																	
50800105	REINFORCEMENT BARS	POUND	50	50																	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1																	
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2																	
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	1		1																
54010406	PRECAST CONCRETE BOX CULVERT 4' X 6'	FOOT	56	56																	

* SPECIALTY ITEM

REVISD 10/22/08