

SUMMARY OF QUANTITIES

P.A.D. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
-22-	135W-21 BS-5	EUILION	282	9
STA.	TO STA.			
FED. ROAD DIST. NO. 5	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			URBAN				CONSTRUCTION TYPE CODE														
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A 100% FED	TUNNEL SIDE WALK REM SFTY-1B 100% CITY	TRAFFIC SIGNALS Y031-1F 100% STATE	SIDEWALK SFTY-1B 50% STATE 50% CITY														
60221700	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 8 GRATE	EACH	5	5																	
60224071	MANHOLES, TYPE A, 6' -DIAMETER, WITH MEDIAN INLET (604106)	EACH	1	1																	
60224446	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1																	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	14	14																	
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	1	1																	
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	16	16																	
60241800	INLETS, TYPE G-1	EACH	1	1																	
60241900	INLETS, TYPE G-1, SPECIAL	EACH	19	19																	
60242100	INLETS, TYPE G-2	EACH	1	1																	
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1																	
60402210	GRATES, TYPE 8	EACH	1	1																	
60405500	FRAMES AND GRATES (INLET G-1)	EACH	66	66																	
60405600	FRAMES AND GRATES (INLET G-2)	EACH	1	1																	
60500040	REMOVING MANHOLES	EACH	1	1																	
60500050	REMOVING CATCH BASINS	EACH	1	1																	
60500060	REMOVING INLETS	EACH	25	25																	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	48.1	48.1																	
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	1028	1028																	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	214.5	214.5																	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	8208.9	8208.9																	
60900515	CONCRETE THRUST BLOCKS	EACH	1	1																	
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	750	750																	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	23.4		23.4																
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4																	
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	1317	1317																	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	46	46																	
66700095	PERMANENT SURVEY MARKERS	EACH	23	23																	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10																	
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	10	10																	
67100100	MOBILIZATION	L SUM	1	1																	

* SPECIALTY ITEM

REVISSED 10-22-08