

# SUMMARY OF QUANTITIES

F.A.S. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-21-RS-5	EULTON	282	7
STA.	TO STA.			
FED. ROAD DIST. NO. 5	BLMBS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			URBAN				CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A 90% FED 10% STATE	TUNNEL SIDE WALK REM 1000-2A 100% CITY	TRAFFIC SIGNALS Y031-1F 100% STATE	SIDEWALK 1000-2A 50% STATE 50% CITY								
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	953	953											
40600990	TEMPORARY RAMP	SQ YD	229.7	229.7											
40603080	HOT - MIX ASPHALT BINDER COURSE, IL - 19 .0, N50	TON	19338.3	19338.3											
40603360	HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N50	TON	4875.4	4875.4											
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	513.2	513.2											
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1284	1284											
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	544	544											
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH PAVEMENT REMOVAL	SQ FT	34868.5				34868.5								
44000100	PAVEMENT REMOVAL	SQ YD	8072	8072											
44000151	HOT - MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD	48546	48546											
44000157	HOT - MIX ASPHALT SURFACE REMOVAL, 2 "	SQ YD	1673	1673											
44000198	HOT - MIX ASPHALT SURFACE REMOVAL, VARIA BLE DEPTH	SQ YD	1011	1011											
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	6973	6973											
44000300	CURB REMOVAL	FOOT	48	48											
44000400	GUTTER REMOVAL	FOOT	1304	1304											
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2337	2337											
44000600	SIDEWALK REMOVAL	SQ FT	35040	8940	26100										
44004000	PAVED DITCH REMOVAL	FOOT	125	125											
44004250	PAVED SHOULDER REMOVAL	SQ YD	4441	4441											
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	185.5	185.5											
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	233.8	233.8											
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	111		111										
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	20510	20510											
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1678	1678											
48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SQ YD	8836	8836											
48203049	HOT - MIX ASPHALT SHOULDERS, 13"	SQ YD	285.6	285.6											
50104400	CONCRETE HEADWALL REMOVAL	EACH	21	21											
50105220	PIPE CULVERT REMOVAL	FOOT	3259.7	3259.7											
50800105	REINFORCEMENT BARS	POUND	50	50											
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1											
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	2	2											
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	1		1										
54010406	PRECAST CONCRETE BOX CULVERT 4' X 6'	FOOT	56	56											

\* SPECIALTY ITEM