CONTRACT NO. 68114

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-2; RS-5	FULTON	282	99
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
GRADES CHECKED
NOTE BOOK
NO.
BY
DATE

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
NOTE BOOK
NO.
STRUCTURE NO'S/ITNS CHKD
BY
DATE

MATCHLINE STA 272+00

MATCHLINE STA 278+00

MIDDLEPARK DR

LONGWOOD DR

MA-GRA-BL DR

UNNAMED DR

CONC.

EOI

EOP

DUCT(FO)

(PAVED OVER)

340 341 342 343 337 338 339 401 402 403 404 405 406

C37 C38 C39 C40 C41 C42

D1 D2 D4 D5 D6

0 50' 100'

SCALE

675

670

665

660

STRUCTURE #337
272+25 RT 33.4 FT
TY A MANHOLE 5 FT TY 8 F&G
CAST ELEV. 666.30
INVERT ELEV. NORTH 662.43
INVERT ELEV. SOUTH 662.43

STRUCTURE #338
272+48 RT 31.0 FT
MANHOLE TY A 5 FT TY 1 CLOSED
CAST ELEV. 667.78
INVERT ELEV. NORTH 662.32
INVERT ELEV. SOUTH 664.52
INVERT ELEV. EAST 662.41
INVERT ELEV. WEST 661.53 (EXIST.)

STRUCTURE #339
273+39 RT 24.0 FT
G-1 INLET SPECIAL
CAST ELEV. 668.43
INVERT ELEV. NORTH 665.41

STRUCTURE #406
277+48 RT 24.0 FT
G-1 INLET SPECIAL
CAST ELEV. 667.75
INVERT ELEV. SOUTH 664.55

15" SS PVC SDR 26 89.3 FT 1.0%

30" SS CL A TY 1
21.7 FT 0.5%

15" SS PVC SDR 26
154.5 FT 0.5%

* CROSS ROAD PIPE (STRUCTURE #341 TO STRUCTURE #338) --> 18" SS PVC SDR 26 65.8 FT 0.5%

668.45 668.37 | 668.46 668.52 | 668.48 668.67 | 668.47 668.82 | 668.46 668.97 | 668.45 669.12 | 668.37 669.18 | 668.24 669.10 | 668.15 668.87 | 668.11 668.61 | 668.03 668.36 | 667.91 668.10 | 667.75 667.85

272+00 272+50 273+00 273+50 274+00 274+50 275+00 275+50 276+00 276+50 277+00 277+50 278+00

PLOT DATE = 8/19/2008
FILE NAME = c:\projects\11700anton\general2.dgn
TIME = 12:42:44 PM
USER NAME = hudelsonne

DRAINAGE AND UTILITIES (WEST SIDE)