

SUMMARY OF QUANTITIES				ROADWAY FAP 645 80% FEDERAL 20% STATE	STRUCTURE SN.062-0072 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				1000-2A	X081-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	39	39	
20200100	EARTH EXCAVATION	CU YD	1775	1775	
20200500	EARTH EXCAVATION (WIDENING)	CU YD	62	62	
20400800	FURNISHED EXCAVATION	CU YD	69	69	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	165		165
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD.	3446	3446	
25000200	SEEDING, CLASS 2	ACRE	0.9	0.9	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90	
25100630	EROSION CONTROL BLANKET	SO YD	4840	4840	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
28000300	TEMPORARY DITCH CHECKS	EACH	4	4	
28000400	PERIMETER EROSION BARRIER	FOOT	1359	1359	
28100109	STONE RIPRAP, CLASS A5	SO YD	1134		1134
28100705	STONE DUMPED RIPRAP, CLASS A3	SO YD.	250	250	
28200200	FILTER FABRIC	SO YD	1134		1134
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SO YD	435	435	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.09	1.09	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	217	217	
40600990	TEMPORARY RAMP	SO YD	36	36	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	945	945	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	158	158	
42001165	BRIDGE APPROACH PAVEMENT	SO YD.	226	226	
42001300	PROTECTIVE COAT	SO YD	368	368	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	142	142	
44000100	PAVEMENT REMOVAL	SO YD	349	349	
44000400	GUTTER REMOVAL	FOOT	238	238	
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SO YD	233	233	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	120	120	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	29	29	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	268		268
50300225	CONCRETE STRUCTURES	CU YD	62.8		62.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	201.3		201.3
50300260	BRIDGE DECK GROOVING	SO YD	465.6		465.6
50300280	CONCRETE ENCASEMENT	CU YD	4.2		4.2
50300300	PROTECTIVE COAT	SO YD	618		618
50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	826.5		826.5
50800105	REINFORCEMENT BARS	POUND	6,480		6,480
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	57,540		57,540
50800515	BAR SPLICERS	EACH	498		498
51201600	FURNISHING STEEL PILES HP12X53	FOOT	242		242
51202305	DRIVING PILES	FOOT	242		242
51203600	TEST PILE STEEL HP12X53	EACH	1		1
51500100	NAME PLATES	EACH	1		1

FILE NAME = ...\\CAD\general\SunQuant.sht
THE UPCHURCH GROUP, INC.

USER NAME = .USER.	DESIGNED -	REVISED -
PLOT SCALE = #SCALE#	DRAWN -	REVISED -
PLOT DATE = 7/31/2008 12:58:03 PM	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
ILLINOIS ROUTE 17 OVER SENACHWINE CREEK			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
645	(105BR)BR	Marshall	71	3
CONTRACT NO. 68479				
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				