

**ITEM NO. 20100110**  
**TREE REMOVAL (6 TO 15) UNITS DIA.**

LOCATION	UNIT
RT STA 334+15 TO 334+23	16
LT STA 333+87 TO 333+96	23
TOTAL = 39	

**ITEM NO. 40600200**  
**BITUMINOUS MATERIAL (PRIME COAT)**

LOCATION	TON
STA 330+50.00 TO 331+45.00	0.13
STA 331+45.00 TO 333+70.00	0.49
STA 333+70.00 TO 333+90.00	0.03
STA 335+90.00 TO 336+10.00	0.03
STA 336+10.00 TO 337+43.00	0.29
STA 337+43.00 TO 338+00.00	0.08
STA 331+45.00 TO 333+70.00	0.03
STA 336+10.00 TO 337+43.00	0.02
TOTAL = 1.09	

**ITEM NO. 44000100 PAVEMENT REMOVAL**

LOCATION	SQ. YD.
RT STA 333+90.00 TO 334+40.14	145
RT STA 335+19.56 TO 335+90.00	204
TOTAL = 349	

**ITEM NO. 66600105**  
**FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS**

LOCATION	EACH
STA 331+00, 60' RT	1
STA 331+50, 65' RT	1
STA 333+00, 60' RT	1
STA 335+00, 60' RT	1
STA 335+50, 70' RT	1
STA 337+50, 70' RT	1
STA 338+00, 53.33' RT	1
STA 332+50, 57.50' LT	1
STA 333+00, 70' LT	1
STA 337+50, 50' LT	1
STA 338+00, 40' LT	1
TOTAL = 11	

**ITEM NO. 28000300**  
**TEMPORARY DITCH CHECKS**

LOCATION	EACH
RT STA 334+40	1
RT STA 335+50	1
LT STA 334+18	1
LT STA 335+43	1
TOTAL = 4	

**ITEM NO. 40600982**  
**HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT**

LOCATION	SQ. YD.
STA 330+50.00 TO 330+80.00	110
STA 337+00.00 TO 338+00.00	107
TOTAL = 217	

**ITEM NO. 44000400 GUTTER REMOVAL**

LOCATION	FOOT
RT STA 333+50.00 TO 332+88	238
TOTAL = 238	

**ITEM NO. 44000920 BIT CONC SHOULDER REMOVAL**

LOCATION	SQ. YD.
RT STA 330+50.00 TO 332+75.00	110
RT STA 332+75.00 TO 334+34.69	53
RT STA 335+56.11 TO 337+20.00	55
RT ENTRANCE STA 338+05 TO 338+28	8
LT ENTRANCE STA 337+93 TO STA 338+45	17
TOTAL = 233	

**ITEM NO. 28000400**  
**PERIMETER EROSION BARRIER**

LOCATION	FOOT
RT STA 330+50 TO 334+74	428
RT STA 335+50 TO 338+00	253
LT STA 330+50 TO 334+26	376
LT STA 334+94 TO 338+00	302
TOTAL = 1359	

**ITEM NO. 40600990 TEMPORARY RAMP**

LOCATION	SQ. YD.
STA 333+65.00 TO 333+70.00	18
STA 336+10.00 TO 336+15.00	18
TOTAL = 36	

**ITEM NO. 48203029**  
**HOT-MIX ASPHALT SHOULDERS, 8"**

LOCATION	SQ. YD.
STA 331+45.00 TO 333+78.16	78
STA 336+18.16 TO 337+43.00	42
TOTAL = 120	

**ITEM NO. X0301512**  
**GUARDRAIL AGGREGATE EROSION CONTROL**

LOCATION	TON
RT STA 331+36 TO 337+57	103
LT STA 332+10 TO 338+08.55	94
TOTAL = 197	

**ITEM NO. 35600716**  
**HMA BASE COURSE WIDENING, 10"**

LOCATION	SQ. YD.
RT STA 330+50.00 TO 331+45.00	42.22
RT STA 331+45.00 TO 333+78.16	77.72
RT STA 336+18.16 TO 337+90.82	57.55
RT STA 337+90.82 TO 338+00.00	5.61
RT STA 338+00.00 TO 338+45.00	40.00
LT STA 330+50.00 TO 333+61.84	103.90
LT STA 336+01.84 TO 337+93.00	63.72
LT STA 337+93.00 TO 338+00.00	4.28
LT STA 338+00.00 TO 338+45.00	40.00
TOTAL = 435.05	

**ITEM NO. 40603335 HOT MIX ASPHALT**  
**SURFACE COURSE MIX "D", N50**

LOCATION	THK	TON
STA 330+50.00 TO 331+45.00	1 1/2" - 3 3/4"	40.34
STA 331+45.00 TO 333+70.00	1 1/2"	54.60
STA 336+10.00 TO 337+43.00	1 1/2"	32.27
STA 337+43.00 TO 338+00.00	1 1/2" - 3 3/4"	24.21
LEFT ENTRANCE	1 1/2"	3.20
RIGHT ENTRANCE	1 1/2"	3.44
TOTAL = 158.06		

**ITEM NO. 48203100**  
**HOT-MIX ASPHALT SHOULDERS**

LOCATION	TON
RT 330+50.00 TO 331+45.00	4.66
RT 337+43.00 TO 337+89.32	2.27
RT 337+89.32 TO 338+00.00	0.55
RT 338+00.00 TO 338+45.00	3.36
LT 330+50.00 TO 333+61.84	8.73
LT 336+01.84 TO 337+43.00	3.95
LT 337+43.00 TO 337+93.21	1.41
LT 337+93.21 TO 338+00.00	0.35
LT 338+00.00 TO 338+45.00	3.36
TOTAL = 28.64	