

ROUTE NO.	SECTION	COUNTY	SHEET	SHEET
F.A.S. 2370 (IL. 26)	I-BR	PUTNAM	65	25
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		

SHEET NO. 8
31 SHEETS

Contract # 68577

BEAM 5

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	95+57.04	2.92 ft.	474.74	474.74
☉ Brg. N. Abut.	95+60.60	2.92 ft.	474.70	474.70
A	95+70.58	2.92 ft.	474.59	474.62
B	95+80.57	2.92 ft.	474.48	474.53
C	95+90.55	2.92 ft.	474.37	474.42
D	96+00.53	2.92 ft.	474.26	474.30
E	96+10.51	2.92 ft.	474.14	474.17
☉ Brg. Pier 1	96+25.20	2.92 ft.	473.98	473.98
F	96+35.18	2.92 ft.	473.87	473.87
G	96+45.17	2.92 ft.	473.76	473.77
H	96+55.15	2.92 ft.	473.65	473.67
I	96+65.13	2.92 ft.	473.54	473.56
J	96+75.11	2.92 ft.	473.43	473.44
K	96+85.10	2.92 ft.	473.32	473.32
☉ Brg. Pier 2	96+95.07	2.92 ft.	473.21	473.21
L	97+05.05	2.92 ft.	473.10	473.11
M	97+15.04	2.92 ft.	472.98	473.02
N	97+25.02	2.92 ft.	472.87	472.92
O	97+35.00	2.92 ft.	472.76	472.81
P	97+44.98	2.92 ft.	472.65	472.69
☉ Brg. S. Abut.	97+57.43	2.92 ft.	472.51	472.51
Bk. S. Abut.	97+60.81	2.92 ft.	472.48	472.48

BEAM 6

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	95+60.05	8.75 ft.	474.94	474.94
☉ Brg. N. Abut.	95+63.60	8.75 ft.	474.90	474.90
A	95+73.55	8.75 ft.	474.79	474.82
B	95+83.50	8.75 ft.	474.68	474.73
C	95+93.45	8.75 ft.	474.57	474.62
D	96+03.39	8.75 ft.	474.46	474.50
E	96+13.34	8.75 ft.	474.35	474.37
☉ Brg. Pier 1	96+27.93	8.75 ft.	474.18	474.18
F	96+37.88	8.75 ft.	474.07	474.07
G	96+47.83	8.75 ft.	473.96	473.98
H	96+57.78	8.75 ft.	473.85	473.87
I	96+67.72	8.75 ft.	473.74	473.76
J	96+77.67	8.75 ft.	473.63	473.64
K	96+87.62	8.75 ft.	473.52	473.52
☉ Brg. Pier 2	96+97.50	8.75 ft.	473.41	473.41
L	97+07.45	8.75 ft.	473.30	473.31
M	97+17.40	8.75 ft.	473.19	473.22
N	97+27.35	8.75 ft.	473.08	473.13
O	97+37.29	8.75 ft.	472.97	473.02
P	97+47.24	8.75 ft.	472.86	472.90
☉ Brg. S. Abut.	97+59.62	8.75 ft.	472.72	472.72
Bk. S. Abut.	97+62.99	8.75 ft.	472.69	472.69

BEAM 7

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Bk. N. Abut.	95+63.04	14.58 ft.	475.14	475.14
☉ Brg. N. Abut.	95+66.58	14.58 ft.	475.10	475.10
A	95+76.49	14.58 ft.	474.99	475.02
B	95+86.41	14.58 ft.	474.88	474.93
C	95+96.32	14.58 ft.	474.77	474.83
D	96+06.24	14.58 ft.	474.66	474.71
E	96+16.15	14.58 ft.	474.55	474.58
☉ Brg. Pier 1	96+30.63	14.58 ft.	474.39	474.39
F	96+40.54	14.58 ft.	474.28	474.28
G	96+50.46	14.58 ft.	474.17	474.18
H	96+60.37	14.58 ft.	474.06	474.08
I	96+70.29	14.58 ft.	473.95	473.97
J	96+80.20	14.58 ft.	473.84	473.85
K	96+90.12	14.58 ft.	473.73	473.73
☉ Brg. Pier 2	96+99.92	14.58 ft.	473.62	473.62
L	97+09.83	14.58 ft.	473.51	473.52
M	97+19.75	14.58 ft.	473.40	473.43
N	97+29.66	14.58 ft.	473.29	473.33
O	97+39.58	14.58 ft.	473.18	473.23
P	97+49.49	14.58 ft.	473.07	473.11
☉ Brg. S. Abut.	97+61.79	14.58 ft.	472.93	472.93
Bk. S. Abut.	97+65.14	14.58 ft.	472.90	472.90

TOP OF SLAB ELEVATIONS
ILLINOIS ROUTE 26 OVER
COFFEE CREEK
F.A.S. ROUTE 2370
SECTION I-BR
PUTNAM COUNTY
STA. 96+59.00
STRUCTURE NO. 078-0046