

F.A.I. SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57 *	DOUGLAS	76	5

\* (15,21-25,21-26,27)RS-1

# SUMMARY OF QUANTITIES

LOCATION OF WORK:

I-57	I-57	I-57	I-57
DOUGLAS COUNTY	DOUGLAS COUNTY	DOUGLAS COUNTY	DOUGLAS COUNTY
Sta. 1386+91.00 to Sta. 547+00	SN 021-0001	SN 021-0005 & SN 021-0006	SN 021-0008
RURAL	RURAL	RURAL	RURAL
90% FED	90% FED	90% FED	90% FED
10% STATE	10% STATE	10% STATE	10% STATE
CONSTRUCTION TYPE CODE: 1000-2A	SFTY-2A	SFTY-2A	SFTY-2A

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	
20400800	FURNISHED EXCAVATION	CU YD	5,365.0	5,365.0
25000210	SEEDING, CLASS 2A	ACRE	20.0	20.0
25000350	SEEDING, CLASS 7	ACRE	20.0	20.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,800.0	1,800.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1,800.0	1,800.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,800.0	1,800.0
25100115	MULCH, METHOD 2	ACRE	20.0	20.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,000.0	2,000.0
28000300	TEMPORARY DITCH CHECKS	EACH	3.0	3.0
28000500	INLET AND PIPE PROTECTION	EACH	3.0	3.0
28100207	STONE RIPRAP, CLASS A4	TON	265.0	265.0
35101400	AGGREGATE BASE COURSE, TYPE B	TON	48.0	48.0
35300505	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/4"	SQ YD	179.0	179.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	58,590.0	58,590.0
40600300	AGGREGATE (PRIME COAT)	TON	1,172.0	1,172.0
40600855	POLYMERIZED LEVELING BINDER (MACHINEMETHOD), N105	TON	840.0	840.0
40600895	CONSTRUCTING TEST STRIP	EACH	2.0	2.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTTJOINT	SQ YD	18,783.0	18,783.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL+ BUTT JOINT	SQ YD	720.0	720.0
40600990	TEMPORARY RAMP	SQ YD	3,959.0	3,959.0
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	45,686.0	45,686.0
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	29,239.0	29,239.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	63.0	63.0
40800030	AGGREGATE (PRIME COAT)	TON	2.0	2.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	90.0	90.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,461.0	1,461.0
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	144,877.0	144,877.0

\* SPECIALTY ITEMS

SHEET 1 OF 4

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 F.A.I. ROUTE 57  
 SECTION (15,21-25,21-26,27)RS-1  
 DOUGLAS COUNTY

SCALE: N/A  
 DATE: 08-12-08

DRAWN BY: JP  
 CHECKED BY: KD

PLOT DATE = 8/21/2008  
 FILE NAME = c:\projects\70465\70465.dgn  
 PLOT SCALE = 1/8" = 1' IN.  
 USER NAME = sheshaun