

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	DOUGLAS	76	23

* (15,21-25,21-26,27)RS-1

SCHEDULE OF QUANTITIES

44000198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH						
LOCATION	STATION	TO	STATION	WIDTH (FOOT)	AREA (SQ YD)	
MAINLINE						
N.B. PASSING LANE	175+13.87	TO	310+00.00	11.0	16,483.0	
N.B. PASSING LANE	330+00.00	TO	360+83.33 (BK)	11.0	3,768.5	
N.B. PASSING LANE	360+87.35 (AH)	TO	379+74.95	11.0	2,307.1	
MAINLINE UNDER SN 021-0046						
N.B. PL, MED & OUT SHLD	379+74.95	TO	382+59.95	31.0	981.7	
MAINLINE						
N.B. PASSING LANE	382+59.95	TO	390+00.00	11.0	904.5	
MAINLINE UNDER SN 021-0045						
N.B. PL, MED & OUT SHLD	436+22.85	TO	439+97.85	31.0	1,291.7	
MAINLINE						
N.B. PASSING LANE	465+72.50	TO	527+81.09	11.0	7,588.3	
N.B. PASSING LANE	531+29.90	TO	547+00.00	11.0	1,919.0	
UNDER SN 021-0024						
S.B. PL, MED & OUT SHLD	1490+89.03	TO	1494+64.03	31.0	1,291.7	
MAINLINE						
S.B. PASSING LANE	175+13.87	TO	322+80.06	11.0	18,047.6	
S.B. PASSING LANE	325+71.38	TO	360+83.33 (BK)	11.0	4,292.4	
S.B. PASSING LANE	360+87.35 (AH)	TO	379+74.95	11.0	2,307.1	
UNDER SN 021-0046						
S.B. PL, MED & OUT SHLD	379+74.95	TO	382+59.95	31.0	981.7	
MAINLINE						
S.B. PASSING LANE	382+59.95	TO	420+96.60	11.0	4,689.2	
S.B. PASSING LANE	423+70.38	TO	436+67.85	11.0	1,585.8	
UNDER SN 021-0045						
S.B. PL, MED & OUT SHLD	436+67.85	TO	439+52.85	31.0	981.7	
MAINLINE						
S.B. PASSING LANE	439+52.35	TO	462+79.00	11.0	2,843.7	
S.B. PASSING LANE	466+24.50	TO	527+82.67	11.0	7,526.7	
S.B. PASSING LANE	531+31.35	TO	547+00.00	11.0	1,917.2	
					TOTAL =	81,708.4
					USE =	81,709.0

X0325285 PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1 1/2"						
LOCATION	STATION	TO	STATION	WIDTH (FOOT)	AREA (SQ YD)	
UNDER SN 015-0063						
N.B. SHOULDER (MED)	1386+91.00	TO	1387+81.00	3.0	30.0	
S.B. SHOULDER (MED)	1386+91.00	TO	1387+81.00	4.0	40.0	
UNDER SN 021-0041						
S.B. SHOULDER (MED)	151+72.00	TO	151+95.00	8.0	20.4	
S.B. SHOULDER (MED)	152+16.00	TO	152+71.00	8.0	48.9	
					TOTAL =	139.3
					USE =	140.0

60300105 FRAMES AND GRATES TO BE ADJUSTED		
LOCATION	STATION	EACH
US 36 RAMP A GORE AREA	512+32.00	1.0
		TOTAL =
		1.0

64200105 SHOULDER RUMBLE STRIP						
LOCATION	STATION	TO	STATION	LENGTH (FOOT)		
NORTHBOUND	RT 1386+91.00	TO	RT 1475+46.98	8,856.0		
NORTHBOUND	RT 1482+23.00	TO	RT 1501+15.00	1,892.0		
NORTHBOUND	RT 119+26.82	TO	RT 125+14.09	587.3		
NORTHBOUND	RT 127+41.55	TO	RT 323+70.06	19,628.5		
NORTHBOUND	RT 324+81.38	TO	RT 360+83.33 (BK)	3,602.0		
NORTHBOUND	RT 360+87.35 (AH)	TO	RT 422+38.00	6,150.7		
NORTHBOUND	RT 423+33.00	TO	RT 463+07.00	3,974.0		
NORTHBOUND	RT 464+30.00	TO	RT 528+33.59	6,403.6		
NORTHBOUND	RT 535+38.00	TO	RT 544+92.00	954.0		
NORTHBOUND	LT 1386+91.00	TO	LT 1430+70.00	4,379.0		
NORTHBOUND	LT 1431+30.00	TO	LT 1510+00.00 (BK)	7,870.0		
NORTHBOUND	LT 117+23.47 (AH)	TO	LT 125+14.09	790.6		
NORTHBOUND	LT 127+41.55	TO	LT 142+90.00	1,548.5		
NORTHBOUND	LT 143+50.00	TO	LT 293+63.00	15,013.0		
NORTHBOUND	LT 294+23.00	TO	LT 323+70.06	2,947.1		
NORTHBOUND	LT 324+81.38	TO	LT 360+83.33 (BK)	3,602.0		
NORTHBOUND	LT 360+87.35 (AH)	TO	LT 422+34.00	6,146.7		
NORTHBOUND	LT 423+29.00	TO	LT 463+23.00	3,994.0		
NORTHBOUND	LT 464+38.00	TO	LT 478+24.00	1,386.0		
NORTHBOUND	LT 478+84.00	TO	LT 528+33.59	4,949.6		
NORTHBOUND	LT 530+77.40	TO	LT 547+00.00	1,622.6		
SOUTHBOUND	RT 1386+91.00	TO	RT 1473+49.73	8,658.7		
SOUTHBOUND	RT 1483+85.00	TO	RT 1502+93.00	1,908.0		
SOUTHBOUND	RT 117+29.54	TO	RT 125+14.09	784.5		
SOUTHBOUND	RT 127+41.55	TO	RT 323+70.06	19,628.5		
SOUTHBOUND	RT 324+81.38	TO	RT 360+83.33 (BK)	3,602.0		
SOUTHBOUND	RT 360+87.35 (AH)	TO	RT 421+83.00	6,095.7		
SOUTHBOUND	RT 422+78.00	TO	RT 463+70.00	4,092.0		
SOUTHBOUND	RT 464+92.00	TO	RT 502+70.76	3,778.8		
SOUTHBOUND	RT 515+46.00	TO	RT 523+15.00	769.0		
SOUTHBOUND	RT 530+77.40	TO	RT 547+00.00	1,622.6		
SOUTHBOUND	LT 1386+91.00	TO	LT 1430+70.00	4,379.0		
SOUTHBOUND	LT 1431+30.00	TO	LT 1510+00.00 (BK)	7,870.0		
SOUTHBOUND	LT 117+23.47 (AH)	TO	LT 125+14.09	790.6		
SOUTHBOUND	LT 127+41.55	TO	LT 142+90.00	1,548.5		
SOUTHBOUND	LT 143+50.00	TO	LT 293+63.00	15,013.0		
SOUTHBOUND	LT 294+23.00	TO	LT 323+70.06	2,947.1		
SOUTHBOUND	LT 324+81.38	TO	LT 360+83.33 (BK)	3,602.0		
SOUTHBOUND	LT 360+87.35 (AH)	TO	LT 421+89.00	6,101.7		
SOUTHBOUND	LT 422+84.00	TO	LT 463+53.00	4,069.0		
SOUTHBOUND	LT 464+77.00	TO	LT 478+24.00	1,347.0		
SOUTHBOUND	LT 478+84.00	TO	LT 528+33.59	4,949.6		
SOUTHBOUND	LT 530+77.40	TO	LT 547+00.00	1,622.6		
					TOTAL =	211,476.5
					USE =	211,477.0

PLOT DATE = 8/21/2008
 FILE NAME = c:\p\projects\45901385 (v8)\78465\cover.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = sheehyjm

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 F.A.I. ROUTE 57
 SECTION (15,21-25,21-26,27)RS-1
 DOUGLAS COUNTY

SCALE: N/A
 DATE: 08-07-08
 DRAWN BY: RC
 CHECKED BY: KD