

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6406	1(BR-2)	MCCLEAN	74	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ACM ROADWAY		ACBRM STRUCTURE	
				URBAN	STP TWO-LANE URBAN ROADWAY 80% FEDERAL 20% STATE 1000-2A	URBAN	HBP TWO-LANE URBAN ROADWAY 80% FEDERAL 20% STATE X071-2A
20200100	EARTH EXCAVATION	CU YD	710		710		0
20400800	FURNISHED EXCAVATION	CU YD	7980		7980		0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	133		133		0
25000200	SEEDING, CLASS 2	ACRE	2.25		2.25		0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	203		203		0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	203		203		0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	203		203		0
25100105	MULCH, METHOD 2	ACRE	2.25		2.25		0
25100630	EROSION CONTROL BLANKET	SO YD	615		615		0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	230		230		0
28000300	TEMPORARY DITCH CHECKS	EACH	10		10		0
28000400	PERIMETER EROSION BARRIER	FOOT	1108		1108		0
28100107	STONE RIPRAP, CLASS A4	SQ YD	1678		166		1512
28200200	FILTER FABRIC	SQ YD	1678		166		1512
3100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	4901		4901		0
3101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	99		99		0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1198		1198		0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	184		184		0
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1749		1749		0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	297		297		0
42001165	BRIDGE APPROACH PAVEMENT	SO YD	266		266		0
42001300	PROTECTIVE COAT	SQ YD	282		282		0
44000100	PAVEMENT REMOVAL	SQ YD	1018		1018		0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	276		276		0
44000700	APPROACH SLAB REMOVAL	SQ YD	174		174		0
44004250	PAVED SHOULDER REMOVAL	SQ YD	489		489		0
44004300	PAVEMENT BREAKING	SO YD	3094		3094		0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	18		18		0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	456		456		0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		0		1
50200100	STRUCTURE EXCAVATION	CU YD	277		0		277
50300100	FLOOR DRAINS	EACH	16		0		16
50300225	CONCRETE STRUCTURES	CU YD	152.1		0		152.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	218.5		0		218.5
50300260	BRIDGE DECK GROOVING	SQ YD	623		0		623

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ACM ROADWAY		ACBRM STRUCTURE	
				URBAN	STP TWO-LANE URBAN ROADWAY 80% FEDERAL 20% STATE 1000-2A	URBAN	HBP TWO-LANE URBAN ROADWAY 80% FEDERAL 20% STATE X071-2A
50300280	CONCRETE ENCASMENT	CU YD	9.8		0		9.8
50300300	PROTECTIVE COAT	SO YD	780		0		780
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		0		1
50500505	STUD SHEAR CONNECTORS	EACH	3276		0		3276
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	63830		0		63830
50800515	BAR SPLICERS	EACH	84		0		84
51201600	FURNISHING STEEL PILES HP12X53	FOOT	1566		0		1566
51202305	DRIVING PILES	FOOT	1566		0		1566
51203600	TEST PILE STEEL HP12X53	EACH	4		0		4
51500100	NAME PLATES	EACH	1		0		1
52100520	ANCHOR BOLTS, 1"	EACH	48		0		48
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1		1		0
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1		0
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1		1		0
54247180	GRATING FOR CONCRETE FLARED END SECTION 42"	EACH	1		1		0
54248510	CONCRETE COLLAR	CU YD	2		2		0
550A0050	STORM SEWERS, CLASS A, TYPE 112"	FOOT	16		16		0
550A0090	STORM SEWERS, CLASS A, TYPE 118"	FOOT	17		17		0
550A0180	STORM SEWERS, CLASS A, TYPE 142"	FOOT	38		38		0
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	68		0		68
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	165		0		165
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1		1		0
60236100	INLETS, TYPE A, TYPE 6 FRAME AND GRATE	EACH	1		1		0
60258000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	2		2		0
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2		2		0
60262800	INLETS TO BE RECONSTRUCTED (SPECIAL)	EACH	2		2		0
60263105	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 3V FRAME AND GRATE	EACH	1		1		0
60500065	REMOVING INLETS, SPECIAL	EACH	1		1		0
60600095	CLASS S1 CONCRETE (OUTLET)	CU YD	6		6		0

* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES
SHEET 1 OF 2**

SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY: CHECKED BY:

PLOT DATE = 8/26/2008
 FILE NAME = c:\p\mca\6503706 (68)\11.DL_2007_submittal\summary.dgn
 PLOT SCALE = 42.383 / IN.
 USER NAME = shulsterj