

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 730
U.S. 51 BR
(CENTER ST.)
&
EMERSON ST.
100% STATE

FAP 730
U.S. 51 BR
(MAIN ST.)
&
EMERSON ST.
100% STATE

FAP 730
U.S. 51 BR
(MAIN ST.)
&
WOOD ST.
100% STATE

CONSTRUCTION TYPE CODE:

Y031-1F
QUANTITY

Y031-1F
QUANTITY

Y031-1F
QUANTITY

CODE NO	ITEM	UNIT	TOTAL QUANTITY	Y031-1F QUANTITY	Y031-1F QUANTITY	Y031-1F QUANTITY
X0326225	PAINT NEW PEDESTRIAN PUSH-BUTTON POST	EACH	6.0	2.0	1.0	3.0
X0326226	PAINT NEW MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, OVER 40 FEET	EACH	1.0		1.0	
X0326227	PAINT NEW MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 1 - UNDER 40 FEET, 1 - OVER 40 FEET	EACH	1.0	1.0		
X8774420	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 38 FT. AND 40 FT. COMBINATION	EACH	1.0	1.0		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	442.0	111.0	198.0	133.0
42400610	TEMPORARY SIDEWALK	SQ FT	297.0	97.0	100.0	100.0
44000600	SIDEWALK REMOVAL	SQ FT	373.0	97.0	156.0	120.0
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	19.0		19.0	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	15.0		15.0	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	14.0		14.0	
67100100	MOBILIZATION	L SUM	1.0	.4	.3	.3
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	.4	.3	.3
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0	.4	.3	.3
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	200.0		200.0	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	198.0		198.0	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40.0		40.0	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	261.0		261.0	
80500100	SERVICE INSTALLATION, TYPE A	EACH	3.0	1.0	1.0	1.0
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	109.0	30.0	42.0	37.0
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	742.0	235.0	366.0	141.0
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	255.0	83.0	95.0	77.0
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	85.0	10.0	47.0	28.0
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	41.0	19.0	22.0	
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	16.0			16.0
81013100	CONDUIT IN TRENCH, 5" DIA., PVC	FOOT	8.0	3.0	2.0	3.0
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	432.0	200.0	151.0	81.0
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	127.0		70.0	57.0
81030100	CONDUIT SPLICE	EACH	1.0		1.0	
81400100	HANDHOLE	EACH	13.0	4.0	6.0	3.0
81400300	DOUBLE HANDHOLE	EACH	3.0	1.0	1.0	1.0
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,256.0	380.0	574.0	302.0
83057180	LIGHT POLE, WOOD, 35 FOOT, CLASS 4	EACH	1.0		1.0	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	620.0	620.0		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,073.0	125.0	540.0	408.0
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,498.0	699.0	1053.0	746.0

FILE NAME =	USER NAME = biggsrd	DESIGNED - RDB	REVISED -
cc:\proj\ecta\d570730\emerson_street.dgn		DRAWN - RDB	REVISED -
PLOT SCALE = 40,0000 ' / IN.		CHECKED -	REVISED -
PLOT DATE = 10/21/2008		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

REVISED SHEET 10/23/08

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
730	(BCS)TS:(622)TS:(622-2)TS	MCLEAN	14	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 70730	