

GENERAL NOTES

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-105.07

EXISTING STATE-OWNED AND MAINTAINED UTILITY LINES ARE SHOWN ON THE PLANS TO INDICATE THEIR PRESENCE AND APPROXIMATE LOCATION. THE CONTRACTOR SHALL NOTIFY THE DISTRICT OPERATIONS ENGINEER TWO WEEKS PRIOR TO COMMENCING ANY EXCAVATION IN THE VICINITY OF THESE LINES. THE STATE WILL THEN LOCATE AND MARK THE HORIZONTAL LOCATIONS OF THE LINES AND PROVIDE ANY AVAILABLE INFORMATION AS TO THEIR DEPTH. SHOULD ANY OF THE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATION, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF THE ENGINEER AND AT NO COST TO THE STATE.

ALSO THERE MAY BE UTILITIES PRESENT WHICH WERE INSTALLED BY THE STATE BUT ARE MAINTAINED BY OTHERS (CITY, TOWN, ETC.) THE APPROXIMATE LOCATIONS OF THESE LINES ARE ALSO SHOWN ON THE PLANS ALONG WITH THE NAME OF THE MAINTAINING AGENCY. THE CONTRACTOR SHALL COORDINATE THE LOCATING OF THESE LINES WITH THE LOCAL AGENCY PRIOR TO COMMENCING ANY EXCAVATION OR BORING IN THEIR VICINITY. SHOULD THESE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATIONS, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF, AND AT NO COST TO, THE LOCAL AGENCY AND THE STATE.

G.N.-107.31

UTILITY LINES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED (QUALITY LEVEL C &/OR QUALITY LEVEL D) AND THE ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY.

UTILITY COMPANIES MAY BE ADJUSTING THEIR FACILITIES DURING CONSTRUCTION. THE CONTRACTOR SHALL COOPERATE WITH THESE ORGANIZATIONS WHILE THESE ADJUSTMENTS ARE BEING PERFORMED. J.U.L.I.E. - JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS SYSTEM (800)892-0123 OR 811.

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

STANDARDS IN THE PLANS

STANDARD	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-01	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
701701-05	URBAN CLOSURE MULTILANE INTERSECTION
701801-03	LANE CLOSURE MULTILANE, CROSSWALK OR SW
701901	TRAFFIC CONTROL DEVICES
720016-01	MAST ARM MOUNTED STREET NAME SIGNS
805001	ELECTRIC SERVICE INSTALLATION DETAILS
814001-01	HANDHOLES
814006-01	DOUBLE HANDHOLES
857001	STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCE
873001-01	TRAFFIC SIGNAL GROUNDING AND BONDING
876001	PEDESTRIAN PUSH BUTTON POST
877001-03	STEEL MAST ARM ASSEMBLY AND POLE
877006-02	STELL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS
878001-06	CONCRETE FOUNDATION DETAILS
880006	TRAFFIC SIGNAL MOUNTING DETAILS - POST AND BRACKET MOUNT
886001	DETECTOR LOOP INSTALLATIONS
886006	TYPICAL LAYOUTS FOR DETECTION LOOPS

INDEX OF SHEETS

1	COVER SHEET
2	GENERAL NOTES, STANDARDS IN THE PLANS, INDEX
3-4	SUMMARY OF QUANTITIES
5-6	TRAFFIC SIGNAL PLANS - CENTER & EMERSON
7	SCHEDULE OF QUANTITIES, BILL OF MATERIALS, PHASE DESIG. DIAGRAM - CENTER & EMERSON
8-9	TRAFFIC SIGNAL PLANS - MAIN & EMERSON
10	SCHEDULE OF QUANTITIES, BILL OF MATERIALS, PHASE DESIG. DIAGRAM - MAIN & EMERSON
11-12	TRAFFIS SIGNAL PLANS - MAIN & WOOD
13	SCHEDULE OF QUANTITIES, BILL OF MATERIALS, PHASE DESIG. DIAGRAM - MAIN & WOOD
14	TRAFFIC SIGNAL DETAILS

FILE NAME = c:\projects\570730\emerson_street.dgn	USER NAME = biggsrd	DESIGNED - RDB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - RDB	REVISED -		730	(8CS)TS(62Z)TS(62Z-2)TS	MCLEAN	14	2
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 70730				
PLOT DATE = 8/22/2008	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.
					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				